

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
A.	Sub Structure Works				
A.1	Site Clearance	2,172.00	Sq.ft		-
	The Contractor shall allow for removal from site of all rubble and debris and any existing foundation etc., and all complete as per directed by the Engineer.				
A.2	Excavation And Earthwork	7,212.00	Cft		-
	Excavation for Lower Ground, foundations including hard surface. The extent is limited from the existing ground level till formation level, De watering, levelling, dressing and ramming the excavation surface and throwing earth clear of edges of excavation and or any lead & lift as per instructions of Engineer in proper grades, all complete as per drawings, specifications, and as directed by the Engineer.				
A.3	Ant termite treatment	3,028.00	Sq.ft		-
	Providing pre constructional anti termite treatment by injecting 30.5% SC with 0.075% on centration complete and creating a continuous barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which appointable laid, surroundings of pipes and conduits etc., complete as per specification and stipulations landowning IS 6313 and as directed by the Engineer.				
A.4	Sand filling	874.00	Cft		-
	Providing and filling good quality Manufactured Sand and 100mm Thickness from approved source including by compacting complete in all respects and as directed by the Engineer.				
A.5	Plain Cement Concrete (P.C.C)	474.00	Cft		-
	Providing and laying plain cement concrete 1:4:8 and 50mm Thickness using PPC cement in foundations, under floor or where require with approved quality 40mm down graded crush and approved quality / sand to give specified strengths including all machine mixing, pouring, compaction & curing including formwork where required, all complete as per drawings,. Specifications & as directed by the Engineer.				
A.6	Plain Cement Concrete (P.C.C)	481.00	Cft		-
	Providing and laying plain cement concrete 1:3:6 and 100mm Thickness using PPC cement in foundations, under floor or where require with approved quality 40mm down graded crush and approved quality / sand to give specified strengths including all machine mixing, pouring, compaction & curing including formwork where required, all complete as per drawings,. Specifications & as directed by the Engineer.				
A.7	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M25 (1:1.5:3), Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete - Footing	1,000.00	Cft		-
	Reinforcement Cement Concrete - Column	242.00	Cft		-
	Reinforcement Cement Concrete - Wall	164.00	Cft		-
	Reinforcement Cement Concrete - Pedestal	21.00	Cft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
	Reinforcement Cement Concrete - Plinth Beam	366.00	Cft		-
	Reinforcement Cement Concrete - Tie Beam	137.00	Cft		-
A.8	Reinforcement works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-500 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer				
	Reinforcement works - Footing	2,000.00	Kg		-
	Reinforcement works - Column	1,452.00	Kg		-
	Reinforcement works - Wall	820.00	Kg		-
	Reinforcement works - Pedestal	105.00	Kg		-
	Reinforcement works - Plinth Beam	1,464.00	Kg		-
	Reinforcement works - Tie Beam	411.00	Kg		-
A.9	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All works up to plinth level)				
	Shuttering Works - Footing	1,059.00	Sq.ft		-
	Shuttering Works - Column	842.00	Sq.ft		-
	Shuttering Works - Wall	455.00	Sq.ft		-
	Shuttering Works - Pedestal	26.00	Sq.ft		-
	Shuttering Works - Plinth Beam	981.00	Sq.ft		-
	Shuttering Works - Tie Beam	370.00	Sq.ft		-
A.10	Brickwork 9" Thk.	317.00	Cft		-
	Providing and laying brick masonry work, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
A.11	Earth filling in Basement (Excavated Earth) - Below Ground Level.	4,801.00	Cft		-
	Providing and filling available earth at site (excavated earth) including dressing, watering and consolidation by compacting 95% of MDD in layers not exceeding 6" in depth complete in all respects and as directed by the Engineer.				
A.12	Earth filling in Basement (Outside Earth) - Above Ground Level.	4,797.00	Cft		-
	Providing and filling good quality local earth from approved source including dressing, watering and consolidation by compacting 95% of MDD in layers not exceeding 6" in depth complete in all respects and as directed by the Engineer.				

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
B.	Super Structure Works - Ground floor				
B.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M25 (1:1.5:3), Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete - Column	258.00	Cft		-
	Reinforcement Cement Concrete - Sill Beam	15.00	Cft		-
	Reinforcement Cement Concrete - Lintel Beam	41.00	Cft		-
	Reinforcement Cement Concrete - Staircase	46.00	Cft		-
	Reinforcement Cement Concrete - Roof beam	355.00	Cft		-
	Reinforcement Cement Concrete - Roof Slab	775.00	Cft		-
B.2	Reinforcement works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-500 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer				
	Reinforcement works - Column	1,548.00	Kg		-
	Reinforcement works - Sill Beam	45.00	Kg		-
	Reinforcement works - Lintel Beam	123.00	Kg		-
	Reinforcement works - Staircase	138.00	Kg		-
	Reinforcement works - Roof beam	1,420.00	Kg		-
	Reinforcement works - Roof Slab	2,325.00	Kg		-
B.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All works up to plinth level)				
	Shuttering Works - Column	896.00	Sq.ft		-
	Shuttering Works - Sill Beam	40.00	Sq.ft		-
	Shuttering Works -Lintel Beam	126.00	Sq.ft		-
	Shuttering Works -Staircase	102.00	Sq.ft		-
	Shuttering Works - Roof beam	855.00	Sq.ft		-
	Shuttering Works -Roof Slab	2,000.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
B.4	AAC Block - 8" Thk.	521.00	Sq.ft		-
	Providing and laying AAC Block works 8" Thk, (Block Size 16"x8"x8") in 1:4 Cement Mortar (1 Cement : 4 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
B.5	AAC Block - 4" Thk.	76.00	Sq.ft		-
	Providing and laying AAC Block works 4" Thk, (Block Size 16"x4"x8") in 1:3 Cement Mortar (1 Cement : 3 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
C	Super Structure Works - First floor				
C.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M25 (1:1.5:3), Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete - Column	186.00	Cft		-
	Reinforcement Cement Concrete - Sill Beam	62.00	Cft		-
	Reinforcement Cement Concrete - Lintel Beam	178.00	Cft		-
	Reinforcement Cement Concrete - Sunshade	14.00	Cft		-
	Reinforcement Cement Concrete - Platform & Loft	26.00	Cft		-
	Reinforcement Cement Concrete - Staircase	46.00	Cft		-
	Reinforcement Cement Concrete - Roof beam	401.00	Cft		-
	Reinforcement Cement Concrete - Roof Slab	709.00	Cft		-
C.2	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-500 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer				
	Reinforcement works - Column	1,116.00	Kg		-
	Reinforcement works - Sill Beam	186.00	Kg		-
	Reinforcement works - Lintel Beam	534.00	Kg		-
	Reinforcement works - Sunshade	42.00	Kg		-
	Reinforcement works - Platform & Loft	78.00	Kg		-
	Reinforcement works - Staircase	138.00	Kg		-
	Reinforcement works - Roof beam	1,604.00	Kg		-
	Reinforcement works - Roof Slab	2,127.00	Kg		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
C.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All works up to plinth level)				
	Shuttering Works - Column	765.00	Sq.ft		-
	Shuttering Works - Sill Beam	191.00	Sq.ft		-
	Shuttering Works -Lintel Beam	581.00	Sq.ft		-
	Shuttering Works -Sunshade	70.00	Sq.ft		-
	Shuttering Works - Platform & Loft	129.00	Sq.ft		-
	Shuttering Works -Staircase	102.00	Sq.ft		-
	Shuttering Works - Roof beam	1,090.00	Sq.ft		-
	Shuttering Works -Roof Slab	1,765.00	Sq.ft		-
C.4	Brickwork 9" Thk.	2,200.00	Sq.ft		-
	Providing and laying brick masonry work, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
C.5	Brickwork 4.5" Thk.	1,052.00	Sq.ft		-
	Providing and laying brick masonry work, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
D	Super Structure Works - Second floor				
D.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M25 (1:1.5:3), Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete - Column	169.00	Cft		-
	Reinforcement Cement Concrete - Sill Beam	55.00	Cft		-
	Reinforcement Cement Concrete - Lintel Beam	159.00	Cft		-
	Reinforcement Cement Concrete - Front Elevation	24.00	Cft		-
	Reinforcement Cement Concrete - Loft	12.00	Cft		-
	Reinforcement Cement Concrete - Staircase	42.00	Cft		-
	Reinforcement Cement Concrete - Roof beam	271.00	Cft		-
	Reinforcement Cement Concrete - Roof Slab	651.00	Cft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
D.2	Reinforcement works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-500 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer				
	Reinforcement works - Column	1,014.00	Kg		-
	Reinforcement works - Sill Beam	165.00	Kg		-
	Reinforcement works - Lintel Beam	477.00	Kg		-
	Reinforcement works - Sunshade	72.00	Kg		-
	Reinforcement works - Platform	36.00	Kg		-
	Reinforcement works - Staircase	126.00	Kg		-
	Reinforcement works - Roof beam	1,084.00	Kg		-
	Reinforcement works - Roof Slab	1,953.00	Kg		-
D.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All works up to plinth level)				
	Shuttering Works - Column	693.00	Sq.ft		-
	Shuttering Works - Sill Beam	162.00	Sq.ft		-
	Shuttering Works -Lintel Beam	505.00	Sq.ft		-
	Shuttering Works -Sunshade	76.00	Sq.ft		-
	Shuttering Works - Loft	58.00	Sq.ft		-
	Shuttering Works -Staircase	96.00	Sq.ft		-
	Shuttering Works - Roof beam	737.00	Sq.ft		-
	Shuttering Works -Roof Slab	1,627.00	Sq.ft		-
D.4	AAC Block - 8" Thk.	2,178.00	Sq.ft		-
	Providing and laying AAC Block works 8" Thk, (Block Size 16"x8"x8") in 1:4 Cement Mortar (1 Cement : 4 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
D.5	AAC Block - 4" Thk.	640.00	Sq.ft		-
	Providing and laying AAC Block works 4" Thk, (Block Size 16"x4"x8") in 1:3 Cement Mortar (1 Cement : 3 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
E	Super Structure Works - Terrace floor				
E.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M25 (1:1.5:3), Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete - Column	57.00	Cft		-
	Reinforcement Cement Concrete - Sill Beam	11.00	Cft		-
	Reinforcement Cement Concrete - Lintel Beam	22.00	Cft		-
	Reinforcement Cement Concrete - Roof beam	59.00	Cft		-
	Reinforcement Cement Concrete - Roof Slab	92.00	Cft		-
E.2	Reinforcement works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-500 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer				
	Reinforcement works - Column	342.00	Kg		-
	Reinforcement works - Sill Beam	33.00	Kg		-
	Reinforcement works - Lintel Beam	66.00	Kg		-
	Reinforcement works - Roof beam	236.00	Kg		-
	Reinforcement works - Roof Slab	276.00	Kg		-
E.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All works up to plinth level)				
	Shuttering - Column	234.00	Sq.ft		-
	Shuttering Works - Sill Beam	30.00	Sq.ft		-
	Shuttering Works -Lintel Beam	94.00	Sq.ft		-
	Shuttering - Roof beam	160.00	Sq.ft		-
	Shuttering - Roof Slab	249.00	Sq.ft		-
E.4	AAC Block - 8" Thk.	513.00	Sq.ft		-
	Providing and laying AAC Block works 8" Thk, (Block Size 16"x8"x8") in 1:4 Cement Mortar (1 Cement : 4 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
F	Finishing Works				
F.1	Ceiling Plastering				
	Providing Ceiling Plastering to Roof Slabs & bottom of waist slab, etc. where ever required, at all levels in cement mortar 1:3, 10mm thick, finishing to line and level with lime rendering, finished smooth, including lead and lift of materials, hydrating the lime 24 hours before starting of work, Chipping, scaffolding, curing, etc., complete as per specifications & as directed by the Engineer				
	Ground floor	1,907.00	Sq.ft		-
	First floor	1,508.00	Sq.ft		-
	Second floor	1,090.00	Sq.ft		-
	Terrace floor	159.00	Sq.ft		-
F.2	Internal Plastering				
	Providing 12 - 15mm thick Plastering on Internal Walls, Columns, Beams, etc., in cement mortar 1:6 (1 Cement : 6 Fine sand), finishing to line and level with lime rendering, finished smooth, at all levels and lifts, hydrating the lime 24 hours before starting of work, scaffolding, curing, necessary hacking and allow for galvanized chicken mesh, 300mm wide and provide 12mm groove at junctions of brick and concrete members, etc., complete as per Technical specifications & as directed by the Engineer				
	Ground floor	861.00	Sq.ft		-
	First floor	4,818.00	Sq.ft		-
	Second floor	3,673.00	Sq.ft		-
	Terrace floor	655.00	Sq.ft		-
F.3	External Plastering				
	Providing 20mm thick Plastering to External surfaces applied in two coats with base coat in cement mortar 1:5 of 12mm thick and a finishing coat of 8mm thick in cement mortar 1:3, mortar mixed with approved waterproofing compound, finishing to line and level with sand faced finishing at all levels including all leads and lifts scaffolding, curing, making & finishing necessary hacking and allow for galvanized chicken mesh, 300mm wide and provide 12mm groove at junctions of brick and concrete members, etc., complete as per specifications & as directed by the Engineer				
	Ground floor	2,412.00	Sq.ft		-
	First floor	2,082.00	Sq.ft		-
	Second floor	2,676.00	Sq.ft		-
	Terrace floor	2,415.00	Sq.ft		-
G	Waterproofing & Thermal Moisture Protection Works				
G.1	Wet area Water proofing - Toilets & Balcony				
	Providing and applying of .Applying one coat of Fosroc Brush bond over the Sunken area flooring and wall surface. The surface should be in saturated condition, After 4 hours of drying second coat of Brush bond will be provided over the first coat, 2 coats brush bond as per Point No 1 & 2 + protective coating / plastering , Providing 15mm thick Protection plaster over a coat of Fosroc WL in CM 1:4 , Watering and curing, stagnant water ponding test for 7 - 10 days, making holes for pipes and core packing as per specification and drawing ,complete as directed and specified.				
	First floor	367.00	Sq.ft		-
	Second floor	112.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
G.2	Brick Jolly Concrete - Toilets				
	Providing and laying plain cement concrete 1:4:8 and 50mm Thickness using PPC cement in foundations, under floor or where require with brick jolly and approved quality / sand to give specified strengths including all machine mixing, pouring, compaction & curing including formwork where required, all complete as per drawings,, Specifications & as directed by the Engineer.				
	Brick Jolly Concrete - Toilets	151.00	Cft		-
G.3	Terrace Water Proofing				
	Providing and applying of .Applying one coat of Fosroc Brush bond over the Sunken area flooring and wall surface. The surface should be in saturated condition, After 4 hours of drying second coat of Brush bond will be provided over the first coat, 2 coats brush bond as per Point No 1 & 2 + protective coating / plastering , Providing 15mm thick Protection plaster over a coat of Fosroc WL in CM 1:4 , Watering and curing, stagnant water ponding test for 7 - 10 days, making holes for pipes and core packing as per specification and drawing ,complete as directed and specified.				
	Terrace floor & Head Room Terrace	1,341.00	Sq.ft		-
G.4	White Cooling Tile Laying				
	Providing and laying White Cooling Tiles in Toilet with ceramic 300 x 300 size with cement mortar 1:4 (1 cement :4 coarse sand) required thickness to match finished floor level mentioned and to match the neighbouring floor finish and jointed with epoxy grout of approved shade from as/existing or equivalent brand all complete as directed complete. Rate to include forming pattern in the flooring like border, cut tiles, Protecting of the tile till hand over date by POP etc. complete as per specifications & as directed by the Engineer				
	Terrace floor & Head Room Terrace	1,341.00	Sq.ft		-
G.5	White Cooling Tile Skirting				
	Providing and fixing White Cooling Tile Skirting of 100mm high of approved make and colour, in skirting on walls, etc. over 1 :3 cement mortar (15mm) base including finishing joints and etc., complete as per specifications & as directed by the Engineer				
	Terrace floor & Head Room Terrace	393.00	Rft		-
H	Flooring & Wall Tile Works				
H.1	Heavy Duty Full Body Non-Slip Vitrified Tile. (2'0"X2'0")				
	Providing and laying Heavy Duty Full Body Non-Slip Vitrified Tile. (2'X2') of size as shown in drawing and Specification, on a bed of 1:4 cement mortar including cement float, filling joints with neat cement slurry, curing, and cleaning etc. complete as per specifications & as directed by the Engineer				
	Car Parking	1,600.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
H.2	Double Glazed Vitrified Tile (4'0"X2'0")				
	Providing and laying Double Glazed Vitrified Tile (4'0"X2'0") laying base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the marble shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	Ground floor	150.00	Sq.ft		-
	First floor	1,424.00	Sq.ft		-
	Second floor	973.00	Sq.ft		-
	Terrace floor	55.00	Sq.ft		-
H.3	Anti skid Ceramic tile				
	Providing and laying Floor Tiles in Toilet with ceramic 300 x 300 size with cement mortar 1:4 (1 cement :4 coarse sand) required thickness to match finished floor level mentioned and to match the neighbouring floor finish and jointed with epoxy grout of approved shade from as/existing or equivalent brand all complete as directed complete. Rate to include forming pattern in the flooring like border, cut tiles, Protecting of the tile till hand over date by POP etc. complete as per specifications & as directed by the Engineer				
	First floor	96.00	Sq.ft		-
	Second floor	55.00	Sq.ft		-
H.4	Granite laying - Staircase				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	Ground floor	110.00	Sq.ft		-
	First floor	110.00	Sq.ft		-
	Second floor	110.00	Sq.ft		-
H.4	Granite Wall Cladding - Lift Entrance				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete , curing etc. complete as per specifications & as directed by the Engineer				
	Ground floor	55.00	Sq.ft		-
	First floor	55.00	Sq.ft		-
	Second floor	55.00	Sq.ft		-
H.5	Granite laying - Kitchen Platform				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	First floor	40.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
H.6	Coloured Glazed Ceramic Tile Laying				
	Providing and laying Coloured Glazed Ceramic Tiles(Designer Tile) in Toilet wall and Pantry wall (thickness to be specified by the manufacturer) with cement mortar 1:4 (1 cement :4 coarse sand) Including pointing the joints with white Cement and Matching Pigment etc. approved shade from as/existing or equivalent brand completes complete as per specifications & as directed by the Engineer				
	First floor	540.00	Sq.ft		-
	Second floor	266.00	Sq.ft		-
H.7	Heavy Duty Full Body Non-Slip Vitrified Tile - Skirting				
	Providing and fixing Heavy Duty Full Body Non-Slip Vitrified Tile. (2'0"X2'0") of 100mm high of approved make and colour, in skirting on walls, etc. over 1 :3 cement mortar (15mm) base including finishing joints and etc., complete as per specifications & as directed by the Engineer				
	Car Parking	100.00	Rft		-
H.8	Vitrified Tile - Skirting				
	Providing and fixing Heavy Duty Full Body Non-Slip Vitrified Tile. (2'0"X2'0") of 100mm high of approved make and colour, in skirting on walls, etc. over 1 :3 cement mortar (15mm) base including finishing joints and etc., complete as per specifications & as directed by the Engineer				
	Ground floor	53.00	Rft		-
	First floor	398.00	Rft		-
	Second floor	410.00	Rft		-
	Terrace floor	32.00	Rft		-
H.9	Granite Skirting				
	Providing and fixing Granite stone skirting of 100mm high of approved make and colour, in skirting on walls, etc. over 1 :3 cement mortar (15mm) base including nosing and finishing joints and etc., complete as per specifications & as directed by the Engineer				
	Ground floor	50.00	Rft		-
	First floor	50.00	Rft		-
	Second floor	50.00	Rft		-
I	Door & Windows				
I.1	Main Door,M.D (4'6"X8'3")				
	Supply and fixing of Teak Wood Frame and one side with Teak finish with Melamine Finish Door and quality fittings and branded safety Lock Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	MD 4.0, Main Door, -Teak Wood	3.00	No		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
I.2	Internal Doors				
	Supply and fixing of Teak Wood (2nd Class) Frame and Designer flush Door with Smooth finish , Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	D 3.0, Internal Door	10.00	No		-
	D 4.0, Internal Door	1.00	No		-
J.3	WPVC Door (2'6"X7'0")				
	Supply and fixing of Waterproof PVC frame and WPVC Door Shutter, Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	D 2.5, Internal Toilet Door - WPVC	4.00	No		-
I.4	UPVC Sliding Door				
	Supply and fixing of UPVC Sliding Door With frame (Wooden Coating) with fixed Glass (as per standard Specification) and , Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	Sliding Door, SD 6.0 Size 6'0" X 7'0"	3.00	No		-
	Sliding Door, SD 9.0 Size 9'0" X 7'0"	3.00	No		-
I.5	UPVC Window				
	Supply and fixing of UPVC Window frame (Wooden Coating) with fixed Glass (as per standard Specification) and , Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	Window, W4.0	6.00	No		-
	Window, W2.6	1.00	No		-
	Window, W2.0	1.00	No		-
	Kitchen Window, KW4.0	1.00	No		-
I.6	UPVC Ventilator				
	Supply and fixing of UPVC Louvers frame with Louver Glass (as per standard Specification) and , Including a fitting, all hardware's require door lock, door stopper, door lock and all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	V 2.0, UPVC Ventilator	6.00	No		-
I.7	Fixed Glass				
	Supply and fixing of fixing Glass with suitable frame with necessary accessories and related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	Fixed Glass Size 4'0" X 7'0" ,F4.0	1.00	No		-
	Fixed Glass Size 8'0" X 5'0" ,F8.0	1.00	No		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
J	Painting Works				
J.1	1 Coat White Cement (External wall)				
	Supply, Cleaning, Scarping and apply the surface of walls with white cement based of approved make and brand (1.5mm thick), etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	2,412.00	Sq.ft		-
	First floor	2,082.00	Sq.ft		-
	Terrace floor	2,676.00	Sq.ft		-
	Terrace floor (Over Head)	2,415.00	Sq.ft		-
J.2	1 Coat Wall Primer (Ceiling & Int. Wall)				
	Supply, Cleaning, Scarping and apply the surface of walls and Ceiling One Coat wall Primer or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	2,768.00	Sq.ft		-
	First floor	6,326.00	Sq.ft		-
	Terrace floor	4,763.00	Sq.ft		-
	Terrace floor (Over Head)	814.00	Sq.ft		-
J.3	2 Coat Putty (Ceiling & Int. Wall)				
	Supply, Cleaning, Scarping and apply the surface of walls 2 Coat Putty or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	2,768.00	Sq.ft		-
	First floor	6,326.00	Sq.ft		-
	Terrace floor	4,763.00	Sq.ft		-
	Terrace floor (Over Head)	814.00	Sq.ft		-
J.4	2 Coat White Emulsion (White) - Ceiling				
	Supply, Cleaning, Scarping and apply the surface of Ceiling two coats using Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	1,907.00	Sq.ft		-
	First floor	1,508.00	Sq.ft		-
	Terrace floor	1,090.00	Sq.ft		-
	Terrace floor (Over Head)	159.00	Sq.ft		-
J.5	2 Coat Internal Emulsion - Int. Wall				
	Supply, Cleaning, Scarping and apply the surface of Internal walls two coats using Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	861.00	Sq.ft		-
	First floor	4,818.00	Sq.ft		-
	Terrace floor	3,673.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
	Terrace floor (Over Head)	655.00	Sq.ft		-
J.6	2 Coat Exterior Emulsion - Ext. Wall				
	Supply, Cleaning, Scarping and apply the surface of External walls two coats using Ace Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Ground floor	2,412.00	Sq.ft		-
	First floor	2,082.00	Sq.ft		-
	Terrace floor	2,676.00	Sq.ft		-
	Terrace floor (Over Head)	2,415.00	Sq.ft		-
J.7	2 Coat Enamel Paint - Grill				
	Supply, Cleaning, Scarping and apply the surface of MS Grill Two coats using Enamel Paint or any approved equivalents over Grill Surface incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Grill Works	763.00	Sq.ft		-
J.8	Varnish Finish - Main Door				
	Supply, Cleaning, Scarping and apply the surface main door and shutter finish with polish, etc., as per Specification and direction of Engineer in Charge.				
	For Main Door	252.00	Sq.ft		-
J.9	Enamel Finish - Internal Door				
	Supply, Cleaning, Scarping and apply the surface of MS Grill Two coats using Enamel Paint or any approved equivalents over Grill Surface incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.				
	Enamel Finish - Internal Door	500.00	Sq.ft		-
K	Metal and Grill Works				
K.1	Window MS Grill Fixing				
	Providing & Fixing Mild Steel Grill in Windows incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Window MS Grill Fixing	509.00	Sq.ft		-
K.2	Stainless Steel Toughened Glass Railing				
	Providing & Fixing Stainless Steel Toughened Glass Railing in Balcony Handrail incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Balcony Grill Fixing (FF-Balcony) - 3ft. Height.	11.00	Rft		-
	Balcony Grill Fixing (FF-Balcony) - 3ft. Height.	50.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
K.3	Stainless Steel Toughened Glass Railing				
	Providing & Fixing Stainless Steel Toughened Glass Railing in wall in Staircase with as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Ground floor	15.00	Rft		-
	First floor	15.00	Rft		-
	Second floor	15.00	Rft		-
K.4	Tinted Glazing With Patterned MS (2"x2") Pergola With Supports				
	Providing & Fixing Tinted Glazing With Patterned with Mild Steel Beams (2"x2") at Pergola incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Terrace Floor	208.00	Sq.ft		-
K.5	UPVC Louvers				
	Providing & Fixing UPVC Louvers at OTS area for Ventilation Purpose incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	UPVC Louvers, Size 12'0" X 1'6"	2.00	Nr.		-
	UPVC Louvers, Size 5'9" X 1'6"	2.00	Nr.		-
	UPVC Louvers, Size 9'9" X 1'6"	1.00	Nr.		-
	UPVC Louvers, Size 14'0" X 1'6"	1.00	Nr.		-
K.6	Mild Steel Roofing - Pergola				
	Providing & Fixing MS Pergola incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Balcony, Dinning Balcony , FF Roof	14.00	Sq.ft		-
	Balcony, Private Balcony, SF Roof	118.00	Sq.ft		-
	Balcony, Study / Library, SF Roof	25.00	Sq.ft		-
K.7	Mild Steel Circular fins fixing Fixing				
	Supply and Installation of Mild Steel Circular fins fixing & 10.5' Height , Rate to include priming coat as well as two coats of enamel paint, incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Front Elevation	273.00	Rft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
K.8	External Wall Cladding Works				
	Supply and Installation of External Wall Cladding Works at Specified Code & Design Incl. Frame System Fixing works incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Front Elevation	225.00	Sq.ft		-
K.9	Corner Slit Glass Fixing				
	Supply and Installation of Corner Slit Glass Fixing Incl. Frame System Fixing works incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Corner Slit Glass Fixing , Size 4'0" X 12'0"	1.00	Nr.		-
	Corner Slit Glass Fixing , Size 8'9" X 2'0"	1.00	Nr.		-
K.10	Structural Glazing Works				
	Supply and fixing of fully Elevation Glazed windows with Aluminium Supporting Frame Including a fitting, all hardware's require all related works as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge				
	Staircase Foyer , Size 4'0" X 31'0"	124.00	Sq.ft		-
L.	Elevational Works				
L.1	Brick Jaali Works				
	Providing & Fixing Brick Jaali Works Works incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Second floor , Balcony	120.00	Sq.ft		-
L.2	Seater Provision				
	Providing & Fixing Seater Provision Works incl. Related finishing Works, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Size 7'0" X 1'0" , First floor , Balcony	1.00	Nr.		-
	Size 5'0" X 1'0" , Second floor , Balcony	2.00	Nr.		-
L.3	Multi Purpose Stage , Concrete Works				
	Providing & Laying Concreting (5" Thick , RCC) Works incl. Related finishing Works, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Second floor Balcony, Size 16'0" X 6'6"	104.00	Sq.ft		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
L.4	Mult Purpose Stage , Brickworks				
	Providing & Laying Brickworks (9" Thick) Works incl. Related finishing Works, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	9" Brick Wall	36.00	Cft		-
L.5	Exposed Concrete Texture Paint Finish Type - 1				
	Providing & apply Exposed Concrete Paint Finish Type - 1 at Elevation wall incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Elevation Works	450.00	Sq.ft		-
L.6	Exposed Concrete Texture Paint Finish Type - 2				
	Providing & apply Exposed Concrete Paint Finish Type - 2 at Elevation wall incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Elevation Works	1,051.00	Sq.ft		-
L.7	Fluted Panel Type Plastering Works				
	Providing & Fixing Fluted Panel Type Plastering Works at Elevation incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Elevation Works	60.00	Sq.ft		-
L.8	Coved Plastering Works				
	Providing & Fixing Coved Plastering Works Works at Balcony Roof incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Elevation Works, Balcony	72.00	Sq.ft		-
L.9	Fluted Wooden False Ceiling Works				
	Providing & Fixing Coved Plastering Works Works at Balcony Roof incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.				
	Ground floor, Car Parking	1,600.00	Sq.ft		-
M	Plumping Works (Inlet, Outlet, CP & Sanitary fittings for Toilets - Brands Parry ware/Jacquar)				
	First floor (Toilet)	3.00	Nr.		-
	First floor (Kitchen Cum Utility)	1.00	Nr.		-
	Second floor (Toilet)	2.00	Nr.		-

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
N	Electrical Works				
	Ground floor	1,885.00	Sq.ft		-
	First floor	1,650.00	Sq.ft		-
	Second floor	1,560.00	Sq.ft		-
	Terrace Floor	220.00	Sq.ft		-
	Total Amount				-
Notes : OPC Cement Basic Rate Rs 390.00 Per Bag Incl. GST, PPC Cement Basic Rate Rs 350.00 Per Bag Incl. GST and Reinforcement Steel Rate Rs 75,000.00 Per Tonne Incl. GST are Considered.					

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
II	ADDITIONAL WORKS				
1	Over Head Tank Works (Capacity 6,500 Litres)	6,500.00	litre		-
	Over Head Tank Works Incl. R.C.C (M25) Column, R.C.C (M25) Base Slab, R.C.C (M25) Wall and R.C.C (M25) Cover Slab with proper Water proof finishing, Internal and external plastering with required Internal and external paint finish and including MH Cover and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
2	Under Ground Sump (Capacity 15,000 Litres)	15,000.00	litre		-
	Under Ground Sump incl. Excavation, Backfilling, Disposal, P.C.C Laying, R.C.C (M25) Base Slab, R.C.C (M25) Wall and R.C.C (M25) Cover Slab with proper Water proof finishing, Internal and external plastering and including MH Cover and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
3	Under Ground Septic Tank (Capacity 14,800 Litres)	14,800.00	litre		-
	Under Ground Septic tank incl. Excavation, Backfilling, Disposal, P.C.C, Brick Wall 9" Thk. and RCC (M20) Cover Slab with Internal and external plastering and including MH Cover and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
4	Compound Wall - Front Side	11.00	Rft		-
	Compound wall works incl. Pile (RCC), earthwork, Sand filling, P.C.C (M10) Laying, R.C.C (M20) Plinth beam, Block Work 8" Up to Basement, Brick Work 6' & 8' Height incl. With Plastering and finishing with Suitable Paint finish and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
5	Compound Wall - Car Parking Entry Gate (14'0"x5'0")	1.00	Set		-
	Supply and Installation of mild steel open able gate (Double door) with one metal primer and two coats enamel finish and related works, etc., as per Specification and direction of Engineer in Charge.				
6	Compound Wall - MS Folding Gate (13'0"x5'0")	1.00	Set		-
	Supply and Installation of mild steel open able gate (Double door) with one metal primer and two coats enamel finish and related works, etc., as per Specification and direction of Engineer in Charge.				
7	Ladder fixing (From Terrace to Head Room Top)	1.00	Item		-
	Supply and Installation of Ladder fixing at Terrace with related works as per specification and direction of engineer in charge				
	TOTAL AMOUNT - ADDITIONAL WORKS				-
	Notes : OPC Cement Basic Rate Rs 390.00 Per Bag Incl. GST, PPC Cement Basic Rate Rs 350.00 Per Bag Incl. GST and Reinforcement Steel Rate Rs 75,000.00 Per Tonne Incl. GST are Considered.				

SAMPLE COPY - PROPOSED RESIDENTIAL BUILDING (G+2)

BILL OF QUANTITY - BOQ

SI No.	Description of Work	Qty	Unit	Rate (M.Sand)	Amount
III	EXTERNAL WORKS				
1	Setback Area - Interlocking Laying	335.00	Sq.ft		-
	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using 50mm thick compacted bed of fine sand, compacting and drive ways or Two Sheeler parking etc. incl. Necessary earth filling required height (3 ft Depth) complete as per specifications & direction of Engineering- Charge.				
2	Kerb Works	20.00	Rft		-
	Providing and fixing at or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centring, shuttering complete. etc. all complete as per the direction of Engineer-in- charge.				
3	Entrance Ramp	90.00	Sq.ft		-
	Entrance Ramp incl. R.C.C (M25) Cover Slab with Brickwork 9"and external plastering and including and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
4	Entrance Steps	24.00	Sq.ft		-
	Entrance Steps incl. Brickwork 9"and external plastering and including and related works, etc., as per Specification and direction of Engineer in Charge. (all rates including leading and lifting)				
TOTAL AMOUNT - EXTERNAL WORKS					-
Notes : OPC Cement Basic Rate Rs 390.00 Per Bag Incl. GST, PPC Cement Basic Rate Rs 350.00 Per Bag Incl. GST and Reinforcement Steel Rate Rs 75,000.00 Per Tonne Incl. GST are Considered.					