

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
A.	Sub Structure Works				
A.1	Site Clearance	220.00	Sqm		
	The Contractor shall allow for removal from site of all rubble and debris and any existing foundation etc., and all complete as per directed by the Engineer.				
A.2	Excavation And Earthwork	262.00	Cum		
	Excavation for Lower Ground, foundations including hard surface. The extent is limited from the existing ground level till formation level, De watering, levelling, dressing and ramming the excavation surface and throwing earth clear of edges of excavation and or any lead & lift as per instructions of Engineer in proper grades, all complete as per drawings, specifications, and as directed by the Engineer.				
A.3	Anti termite treatment	355.00	Sqm		
	Providing pre constructional anti termite treatment by injecting 30.5% SC with 0.075% on centration complete and creating a continuous barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which appointable laid, surroundings of pipes and conduits etc., complete as per specification and stipulations landowning IS 6313 and as directed by the Engineer.				
A.4	Road Base Filling	13.00	Cum		
	Supplying, spreading, and compacting Road Base in layers up to 100 mm compacted depth to 98% MDD, including watering, rolling, labor, transport, and testing as per specifications in all respects and as directed by the Engineer.				
A.5	Plain Cement Concrete (P.C.C)	23.00	Cum		
	Providing and laying plain cement concrete 1:4:8 and 100mm Thickness using PPC cement in foundations, under floor or where require with approved quality 40mm down graded crush and approved quality / sand to give specified strengths including all machine mixing, pouring, compaction & curing including formwork where required, all complete as per drawings,. Specifications & as directed by the Engineer.				
A.6	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M30, Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete (M30) - Footing	44.00	Cum		
	Reinforcement Cement Concrete (M30) - Pedestal	8.00	Cum		
	Reinforcement Cement Concrete (M30) - Column	4.00	Cum		
	Reinforcement Cement Concrete (M30) - Tie Beam	15.00	Cum		
	Reinforcement Cement Concrete (M30) - Lift Pit Wall	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Grade Slab	14.00	Cum		
A.7	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-550 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer. (Brand : ARS & ISTEEL)				
	Reinforcement Works - Footing	3,300.00	Kg		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
	Reinforcement Works - Pedestal	1,200.00	Kg		
	Reinforcement Works - Column	700.00	Kg		
	Reinforcement Works - Tie Beam	1,125.00	Kg		
	Reinforcement Works - Lift Pit Wall	250.00	Kg		
	Reinforcement Works - Grade Slab	1,050.00	Kg		
A.8	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All Works up to plinth level)				
	Shuttering Works - Footing	77.00	Sqm		
	Shuttering Works - Pedestal	68.00	Sqm		
	Shuttering Works - Column	37.00	Sqm		
	Shuttering Works - Tie Beam	128.00	Sqm		
	Shuttering Works - Lift Pit Wall	14.00	Sqm		
	Shuttering Works - Grade Slab	13.00	Sqm		
A.9	Earth filling in Basement (Available Earth)	173.00	Cum		
	Providing and filling available earth at site (excavated earth) including dressing, watering and consolidation by compacting 95% of MDD in layers not exceeding 6" in depth complete in all respects and as directed by the Engineer.				
A.10	Earth filling in Basement (Local Earth)	77.00	Cum		
	Providing and filling good quality local earth from approved source including dressing, watering and consolidation by compacting 95% of MDD in layers not exceeding 6" in depth complete in all respects and as directed by the Engineer.				
A.11	Brickwork 230mm Thk.	6.00	Cum		
	Providing and laying brick masonry work, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
A.12	12mm Thick Flexible Sheet Laying-150mm Depth	128.00	Rm		
	Providing and laying 12 mm thick flexible sheet over a prepared surface, laid to proper slopes and contours. The process includes preparing the surface by cleaning all loose debris, unrolling and overlapping the sheets as per manufacturer specifications, and heat-welding/joining the edges securely. The item includes laying the sheet into a 150 mm depth excavated anchor trench, backfilling, and compacting the trench with approved material, all complete as directed by the Engineer-in-Charge.				
A.13	Polyethelene Sheet Laying	209.00	Sqm		
	Providing and laying 12mm thick Polyethylene (PE) sheet / membrane to act as a damp-proof layer/vapor barrier over a prepared horizontal or vertical surface. The scope of work includes thoroughly cleaning and leveling the underlying surface, removing all sharp protrusions, unrolling the sheets with a minimum 150mm overlap at all joints, and sealing the laps completely with approved pressure-sensitive waterproof adhesive tape. The work complete in all respects as per technical specifications and as directed by the Engineer-in-Charge				

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
B.	Super Structure Works - Ground floor				
B.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M20, Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete (M30) - Column	16.00	Cum		
	Reinforcement Cement Concrete (M30) - Sill Beam	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Lintel Beam	4.00	Cum		
	Reinforcement Cement Concrete (M30) - Kitchen Platform & Loft	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Sunshade	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Ramp & Steps	3.00	Cum		
	Reinforcement Cement Concrete (M30) - Staircase	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof beam	12.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof Slab	28.00	Cum		
B.2	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-550 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer. (Brand : ARS & ISTEEL)				
	Reinforcement Works - Column	2,800.00	Kg		
	Reinforcement Works - Sill Beam	150.00	Kg		
	Reinforcement Works - Lintel Beam	300.00	Kg		
	Reinforcement Works - Kitchen Platform & Loft	75.00	Kg		
	Reinforcement Works - Sunshade	75.00	Kg		
	Reinforcement Works - Ramp & Steps	225.00	Kg		
	Reinforcement Works - Staircase	200.00	Kg		
	Reinforcement Works - Roof beam	1,800.00	Kg		
	Reinforcement Works - Roof Slab	2,800.00	Kg		
B.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All Works up to plinth level)				
	Shuttering Works - Column	137.00	Sqm		
	Shuttering Works - Sill Beam	17.00	Sqm		
	Shuttering Works - Lintel Beam	43.00	Sqm		
	Shuttering Works - Kitchen Platform & Loft	9.00	Sqm		
	Shuttering Works - Sunshade	6.00	Sqm		
	Shuttering Works - Ramp & Steps	10.00	Sqm		
	Shuttering Works - Staircase	14.00	Sqm		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
	Shuttering Works - Roof beam	101.00	Sqm		
	Shuttering Works -Roof Slab	196.00	Sqm		
B.4	Brickwork 230mm Thk.	30.00	Cum		
	Providing and laying brick masonry work 230mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
B.5	Brickwork 115mm Thk.	89.00	Sqm		
	Providing and laying brick masonry work 115mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
C	Super Structure Works - First floor				
C.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M30, Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete (M30) - Column	16.00	Cum		
	Reinforcement Cement Concrete (M30) - Sill Beam	3.00	Cum		
	Reinforcement Cement Concrete (M30) - Lintel Beam	6.00	Cum		
	Reinforcement Cement Concrete (M30) - Sunshade	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Kitchen Platform & Loft	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof beam	12.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof Slab	28.00	Cum		
C.2	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-550 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer. (Brand : ARS & ISTEEL)				
	Reinforcement Works - Column	2,800.00	Kg		
	Reinforcement Works - Sill Beam	225.00	Kg		
	Reinforcement Works - Lintel Beam	450.00	Kg		
	Reinforcement Works - Sunshade	75.00	Kg		
	Reinforcement Works - Kitchen Platform & Loft	150.00	Kg		
	Reinforcement Works - Roof beam	150.00	Kg		
	Reinforcement Works - Roof Slab	200.00	Kg		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
C.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All Works up to plinth level)				
	Shuttering Works - Column	142.00	Sqm		
	Shuttering Works - Sill Beam	25.00	Sqm		
	Shuttering Works - Lintel Beam	65.00	Sqm		
	Shuttering Works - Sunshade	13.00	Sqm		
	Shuttering Works - Kitchen Platform & Loft	18.00	Sqm		
	Shuttering Works - Roof beam	101.00	Sqm		
	Shuttering Works- Roof Slab	196.00	Sqm		
C.4	Brickwork 230mm Thk.	44.00	Cum		
	Providing and laying brick masonry work 230mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
C.5	Brickwork 115mm Thk.	106.00	Sqm		
	Providing and laying brick masonry work 115mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
D	Super Structure Works - Second floor				
D.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M20, Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete (M30) - Column	16.00	Cum		
	Reinforcement Cement Concrete (M30) - Sill Beam	3.00	Cum		
	Reinforcement Cement Concrete (M30) - Lintel Beam	6.00	Cum		
	Reinforcement Cement Concrete (M30) - Sunshade	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Kitchen Platform & Loft	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof beam	11.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof Slab	28.00	Cum		
D.2	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-550 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer. (Brand : ARS & ISTEEL)				
	Reinforcement Works - Column	2,800.00	Kg		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
	Reinforcement Works - Sill Beam	225.00	Kg		
	Reinforcement Works - Lintel Beam	450.00	Kg		
	Reinforcement Works - Sunshade	75.00	Kg		
	Reinforcement Works - Kitchen Platform & Loft	150.00	Kg		
	Reinforcement Works - Roof beam	150.00	Kg		
	Reinforcement Works - Roof Slab	200.00	Kg		
D.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All Works up to plinth level)				
	Shuttering Works - Column	142.00	Sqm		
	Shuttering Works - Sill Beam	25.00	Sqm		
	Shuttering Works - Lintel Beam	65.00	Sqm		
	Shuttering Works - Sunshade	13.00	Sqm		
	Shuttering Works - Kitchen Platform & Loft	18.00	Sqm		
	Shuttering Works - Roof beam	94.00	Sqm		
	Shuttering Works- Roof Slab	196.00	Sqm		
D.4	Brickwork 230mm Thk.	44.00	Cum		
	Providing and laying brick masonry work 230mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
D.5	Brickwork 115mm Thk.	106.00	Sqm		
	Providing and laying brick masonry work 115mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
E	Super Structure Works - Terrace floor				
E.1	Reinforcement Cement Concrete				
	Providing and laying smooth finished reinforced cement concrete M20, Design Mix 28 days cylinder strengths with Portland Pozzolana cement with approved quality 3/4" down graded crush and approved quality sand meeting with the specifications for required concrete strength including required Reinforcement, and all mixing, pouring, rodding, compaction with vibrators, and curing, all complete with all necessary measures to - produce concrete to true lines, levels, and plumb all as per drawings, specifications & as directed by the Engineer				
	Reinforcement Cement Concrete (M30) - Column	13.00	Cum		
	Reinforcement Cement Concrete (M30) - Sill Beam	2.00	Cum		
	Reinforcement Cement Concrete (M30) - Lintel Beam	3.00	Cum		
	Reinforcement Cement Concrete (M30) - Sunshade	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Kitchen Platform & Loft	1.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof beam	7.00	Cum		
	Reinforcement Cement Concrete (M30) - Roof Slab	17.00	Cum		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
E.2	Reinforcement Works				
	Providing, straightening, cutting, fabricating, and tying in position, High Yield Strength Deformed steel reinforcement bar, FE-550 in foundation, and up to 15 Mtr. height. Rate to include cost of bending, binding with 18 SWG annealed wire at all levels, i/c wastage, and provision of spacers and Cover blocks of required thicknesses. Approved make or equivalent with Incl. lifts and leads all as per drawings, specifications & as directed by the Engineer. (Brand : ARS & ISTEEL)				
	Reinforcement Works - Column	1,820.00	Kg		
	Reinforcement Works - Sill Beam	150.00	Kg		
	Reinforcement Works - Lintel Beam	225.00	Kg		
	Reinforcement Works - Sunshade	75.00	Kg		
	Reinforcement Works - Kitchen Platform & Loft	75.00	Kg		
	Reinforcement Works - Roof beam	875.00	Kg		
	Reinforcement Works - Roof Slab	1,700.00	Kg		
E.3	Shuttering Works				
	Providing and fixing centring and shuttering for concrete work (reinforced concrete only) including strutting, propping, bracing, bolting tie bolt / spring coil / plastic cone, wedging, easing, striking, removal and for coating with approved mineral shuttering oil (REEBOL of FOSROC / equivalent) to prevent adhesion etc, complete. (All Works up to plinth level)				
	Shuttering Works - Column	115.00	Sqm		
	Shuttering Works - Sill Beam	15.00	Sqm		
	Shuttering Works - Lintel Beam	39.00	Sqm		
	Shuttering Works - Sunshade	5.00	Sqm		
	Shuttering Works - Kitchen Platform & Loft	9.00	Sqm		
	Shuttering Works - Roof beam	61.00	Sqm		
	Shuttering Works- Roof Slab	117.00	Sqm		
E.4	Brickwork 230mm Thk.	48.00	Cum		
	Providing and laying brick masonry work 230mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
E.5	Brickwork 115mm Thk.	53.00	Sqm		
	Providing and laying brick masonry work 115mm Thk, good quality approved bricks in 1:6 Cement Mortar (1 Cement : 6 Coarse Sand by volume) in true line, level and plumb for wall, complete with necessary scaffolding, raking of joints, curing etc., Rate to include soaking of bricks adequately before construction, complete as directed and specified.				
F	Finishing Works				
F.1	Ceiling Plastering				
	Providing Ceiling Plastering to Roof Slabs & bottom of waist slab, etc. where ever required, at all levels in cement mortar 1:3, 10mm thick, finishing to line and level with lime rendering, finished smooth, including lead and lift of materials, hydrating the lime 24 hours before starting of work, Chipping, scaffolding, curing, etc., complete as per specifications & as directed by the Engineer				
	Ground Floor	155.00	Sqm		
	First Floor	155.00	Sqm		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
	Second Floor	155.00	Sqm		
	Terrace Floor	90.00	Sqm		
F.2	Internal Plastering				
	Providing 12 - 15mm thick Plastering on Internal Walls, Columns, Beams, etc., in cement mortar 1:6 (1 Cement : 6 Fine sand), finishing to line and level with lime rendering, finished smooth, at all levels and lifts, hydrating the lime 24 hours before starting of work, scaffolding, curing, necessary hacking and allow for galvanized chicken mesh, 300mm wide and provide 12mm groove at junctions of brick and concrete members, etc., complete as per Technical specifications & as directed by the Engineer				
	Ground Floor	496.00	Sqm		
	First Floor	643.00	Sqm		
	Second Floor	643.00	Sqm		
	Terrace Floor	371.00	Sqm		
F.3	External Plastering				
	Providing 20mm thick Plastering to External surfaces applied in two coats with base coat in cement mortar 1:5 of 12mm thick and a finishing coat of 8mm thick in cement mortar 1:3, mortar mixed with approved waterproofing compound, finishing to line and level with sand faced finishing at all levels including all leads and lifts scaffolding, curing, making & finishing necessary hacking and allow for galvanized chicken mesh, 300mm wide and provide 12mm groove at junctions of brick and concrete members, etc., complete as per specifications & as directed by the Engineer				
	Ground Floor	168.00	Sqm		
	First Floor	194.00	Sqm		
	Second Floor	194.00	Sqm		
	Terrace Floor	316.00	Sqm		
G	Waterproofing & Roof Tiling Works				
G.1	Wet area Water proofing - Toilets	71.00	Sqm		
	Providing and applying of .Applying one coat of Fosroc Brush bond over the Sunken area flooring and wall surface. The surface should be in saturated condition, After 4 hours of drying second coat of Brush bond will be provided over the first coat, 2 coats brush bond as per Point No 1 & 2 + protective coating / plastering , Providing 15mm thick Protection plaster over a coat of Fosroc WL in CM 1:4 , Watering and curing, stagnant water ponding test for 7 - 10 days, making holes for pipes and core packing as per specification and drawing ,complete as directed and specified.				
G.2	Weathering Course and Water proof (one Coat) Works	174.00	Sqm		
	Weathering course with brick jelly lime concrete in the proportion of 2.5:1 over roof including giving necessary slope, soaking in jiggery and gallnut water, well beaten with wooden beaters, incl. cost of all materials and curing etc. complete.				
G.3	White Cooling Tile Works	174.00	Sqm		
	Providing and laying White Cooling Tiles in Roof Terrace area 300 x 300 size with cement mortar 1:4 (1 cement :4 coarse sand) required thickness to match finished floor level mentioned and to match the neighbouring floor finish and jointed with epoxy grout of approved shade from as/existing or equivalent brand all complete as directed complete. Rate to include forming pattern in the flooring like border, cut tiles, Protecting of the tile till hand over date by POP etc. complete as per specifications & as directed by the Engineer				

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
G.4	White Cooling Tile Works (Skirting)	80.00	Rm		
	Providing and laying White Cooling Tiles in Roof Terrace area with minimum 100mm height with cement mortar 1:4 (1 cement :4 coarse sand) required thickness to match finished floor level mentioned and to match the neighbouring floor finish and jointed with epoxy grout of approved shade from as/existing or equivalent brand all complete as directed complete. Rate to include forming pattern in the flooring like border, cut tiles, Protecting of the tile till hand over date by POP etc. complete as per specifications & as directed by the Engineer				
H	Flooring & Wall Tile Works				
H.1	Parking Tile Laying	72.00	Sqm		
	Providing and laying heavy-duty, anti-skid car parking tiles of approved make (e.g., Somany, Kajaria, or RAK) and approved color/pattern, with a minimum thickness of 15 mm and compressive strength ≥ 35 MPa, made by table vibratory method using 50mm thick compacted bed of fine sand, compacting and drive ways or Two Sheeler parking etc. incl. Necessary earth filling required height (2 ft Depth) complete as per specifications & direction of Engineering- Charge.				
H.2	Vitrified Tile flooring				
	Providing and laying 1st quality Vitrified Tiles (size 600*600) or of approved brand (e.g., Kajaria, Somany) and shade, laid on to average thick CM (1 cement: 4 coarse sand) base, including cementing the joints with white cement/epoxy grout matching the shade of the tile, curing, cleaning, and all labor complete to specifications complete as per specifications & as directed by the Engineer				
	Ground Floor	68.00	Sqm		
	First Floor	131.00	Sqm		
	Second Floor	131.00	Sqm		
	Terrace Floor	82.00	Sqm		
H.3	Anti skid Ceramic tile				
	Providing and laying Floor Tiles in Toilet with ceramic (600 x 1200mm) size with cement mortar 1:4 (1 cement :4 coarse sand) required thickness to match finished floor level mentioned and to match the neighbouring floor finish and jointed with epoxy grout of approved shade from as/existing or equivalent brand all complete as directed complete. Rate to include forming pattern in the flooring like border, cut tiles, Protecting of the tile till hand over date by POP etc. complete as per specifications & as directed by the Engineer				
	Ground Floor	8.00	Sqm		
	First Floor	17.00	Sqm		
	Second Floor	17.00	Sqm		
	Terrace Floor	9.00	Sqm		
H.4	Glazed Wall Tile				
	Providing and laying Coloured Glazed Ceramic Tiles(300X450mm) in Toilet wall and Pantry wall (thickness to be specified by the manufacturer) with cement mortar 1:4 (1 cement :4 coarse sand) Including pointing the joints with white Cement and Matching Pigment etc. approved shade from as/existing or equivalent brand completes complete as per specifications & as directed by the Engineer				
	Ground Floor	50.00	Sqm		
	First Floor	89.00	Sqm		
	Second Floor	89.00	Sqm		
	Terrace Floor	39.00	Sqm		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
H.5	Granite Laying				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	Ground Floor	13.00	Sqm		
	First Floor	13.00	Sqm		
	Second Floor	13.00	Sqm		
H.6	Granite Laying - Kitchen Platform				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid in Kitchen Platform and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	Ground Floor	6.00	Sqm		
	First Floor	11.00	Sqm		
	Second Floor	11.00	Sqm		
	Terrace Floor	6.00	Sqm		
H.7	Granite Laying - Skirting				
	Granite laying over 20mm thick base of cement mortar 1:4 (1 cement :4 coarse sand) laid and jointed with white cement mortar 1:2 (1 white cement: 2 marble dust)with an admixture of pigment to match the Granite shade including rubbing and polishing complete and also POP protective coat to prevent scratches, curing etc. complete as per specifications & as directed by the Engineer				
	Ground Floor	11.00	Rm		
	First Floor	11.00	Rm		
	Second Floor	11.00	Rm		
H.8	Vitrified Tile -Skirting				
	Providing and fixing vitrified tile skirting (typically 100-150mm height) using high-quality approved vitrified tiles (double charge/full body, conforming to IS:15622) fixed on 10-15mm cement mortar (1:3 or 1:4), finished with matched pigment joints, including cleaning, cutting, and waste disposal and all labor complete to specifications complete as per specifications & as directed by the Engineer				
	Ground Floor	95.00	Rm		
	First Floor	138.00	Rm		
	Second Floor	138.00	Rm		
	Terrace Floor	80.00	Rm		
H.9	Lift Facia				
	Providing and fixing premium-grade lift facia wall cladding of approved make, shade, and design (e.g., Kajaria, Somany, or approved marble/granite variety) up to the door height, securely anchored to the masonry or concrete surface complete as per specifications & as directed by the Engineer				
	Ground Floor	3.00	Sqm		
	First Floor	3.00	Sqm		
	Second Floor	3.00	Sqm		
	Terrace Floor	3.00	Sqm		
H.10	Parking Tile-Skirting	7.00	Rm		
	Providing and fixing premium-grade lift facia wall cladding of approved make, shade, and design (e.g., Kajaria, Somany, or approved marble/granite variety) up to the door height, securely anchored to the masonry or concrete surface complete as per specifications & as directed by the Engineer				

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
I	Door & Windows				
I.1	Entrance Gate, EG (1200 X2100)	1.00	Nr.		
	Providing, fabricating, supplying, and installing a heavy-duty architectural main entrance gate of approved design, drawing, and height, constructed using high-quality structural hollow steel sections (MS-304) or heavy wrought iron framing, complete with internal infill panels, robust hinges, locking mechanisms, and premium protective coatings as per direction of Engineer in Charge.				
I.2	Teak Wood Door				
	Providing, fabricating, supplying, and installing premium-grade solid Teak Wood door shutters (minimum 38mm to 45mm finished thickness) of approved architectural design, panels, and styles, hung securely on factory-seasoned 1st Class Class Teak Wood (CP Teak / Plantation Teak) frames of specified section size. Rate to include all materials, fabrication, and installation, etc. completed as required in any floor as per direction of Engineer in Charge.				
	Main Door MD1, (1100 X2100)	4.00	Nr.		
	Main Door MD2, (1050 X2100)	3.00	Nr.		
I.3	Internal Flush Door D1, (900 X2100)	18.00	Nr.		
	Providing and fixing 35mm thick solid core flush door shutters of approved make (e.g., Greenply, CenturyPly, or Kitply), conforming to IS: 2202 (Part I), finished with 1.0mm thick decorative laminate or veneer on both faces, hung securely on factory-seasoned 2nd Class Teak Wood (CP Teak) frames of specified section size. completed as required in any floor as per direction of Engineer in Charge.				
I.4	PVC Door D2, (800 X 2100)	15.00	Nr.		
	Providing and fixing factory-made 30mm thick moulded PVC door shutter (wood-free). The shutter shall consist of a frame made from 19-gauge M.S. tubes (size 20mm x 40mm) for stiles, top, and bottom rails, coated with metal primer. The internal panel consists of a 20mm thick multi-chamber hollow PVC section bonded with solvent cement to 5mm thick moulded PVC sheets (density 600 kg/cbm). All edges must be sealed with 10mm thick PVC lipping. The rate includes the cost of fabrication, supply, and installation with three stainless steel butt hinges and all necessary hardware etc. completed as required in any floor as per direction of Engineer in Charge.				
I.5	UPVC Window, W (900mm X 1200mm)				
	Providing and fixing in position a Double Leaf uPVC Casement Window with an integrated security grill. The window is to be fabricated from multi-chambered uPVC profiles (minimum 2.0mm to 2.5mm wall thickness) reinforced with 1.6mm G.I. sections. The assembly includes 5mm to 6mm thick toughened clear glass secured with EPDM gaskets. A security grill made of 10mm x 10mm M.S. square bars or an equivalent powder-coated ornamental design shall be integrated into the frame. Hardware includes stainless steel friction stays, an espagnolette multi-point locking system, and handles. Rate includes all materials, fabrication, G.I. fasteners, and weather-proof silicone sealant as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				
	Window W, (1800 X 1200)	24.00	Nr.		
	Window W, (1500 X 1200)	3.00	Nr.		
	Window W, (1100 X 1200)	6.00	Nr.		
I.6	UPVC Vendilator V, (600 X 600)	16.00	Nr.		
	Providing and fixing in position a Double Leaf uPVC Casement Window with an integrated security grill. The window is to be fabricated from multi-chambered uPVC profiles (minimum 2.0mm to 2.5mm wall thickness) reinforced with 1.6mm G.I. sections. The assembly includes 5mm to 6mm thick toughened clear glass secured with EPDM gaskets. A security grill made of 10mm x 10mm M.S. square bars or an equivalent powder-coated ornamental design shall be integrated into the frame. Hardware includes stainless steel friction stays, an espagnolette multi-point locking system, and handles. Rate includes all materials, fabrication, G.I. fasteners, and weather-proof silicone sealant as per Drawing and Architect Specifications, etc. completed as required in any floor as per direction of Engineer in Charge.				

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
I.7	UPVC Sliding Door SD, (2000 X 2100) Providing, fabricating, supplying, and installing heavy-duty, multi-chambered UPVC sliding door systems of approved make (e.g., Fenesta, Deceuninck, Rehau, or Profine/Koemmerling), in approved profile colors (White/Dark Oak Woodgrain /Anthracite Grey), complete with reinforced steel chassis, premium glazing, EPDM gaskets, and specialized multi-point locking hardware etc. completed as required in any floor as per direction of Engineer in Charge.	3.00	Nr.		
J.	Painting Works				
J.1	1 Coat White Cement (Ceiling) Supply, Cleaning, Scarping and apply the surface of walls with white cement based wall putty of approved make and brand (1.5mm thick), etc., as per Specification and direction of Engineer in Charge.	555.00	Sqm		
J.2	1 Coat Wall Primer (Ceiling & Int. Wall) Supply, Cleaning, Scarping and apply the surface of walls and Ceiling One Coat wall Primer or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.	2,708.00	Sqm		
J.3	2 Coat Putty (Ceiling & Int. Wall) Supply, Cleaning, Scarping and apply the surface of walls 2 Coat Putty or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.	2,708.00	Sqm		
J.4	2 Coat Primer Emulsion (White) - Ceiling Supply, Cleaning, Scarping and apply the surface of Ceiling two coats using Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.	555.00	Sqm		
J.5	2 Coat Primer Emulsion - Int. Wall Supply, Cleaning, Scarping and apply the surface of Internal walls two coats using Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.	2,153.00	Sqm		
J.6	2 Coat Epoxy Paint-External wall Supply, Cleaning, Scarping and apply the surface of External walls two coats using Ace Emulsion Paint or any approved equivalents over new surface of walls and ceilings incl. cost of all materials, brush, scaffolding and etc., as per Specification and direction of Engineer in Charge.	872.00	Sqm		
K.	Metal and Grill Works				
K.1	Staircase Handrail Providing & Fixing Stainless Steel Handrail fixing in wall in Staircase with as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.	8.00	Rm.		
K.2	Window MS Grill Fixing Providing & Fixing Mild Steel Grill in Windows incl. cost of all materials, Touch-up, scaffolding and etc., as per Specification and direction of Engineer in Charge.as per Specification and direction of Engineer in Charge.	71.00	Sqm		
K.3	Balcony Toughned Glass Handrail Providing, fabricating, supplying, and installing a premium-grade architectural Toughened Safety Glass handrail assembly for balconies of approved design, height (minimum 1050mm to 1200mm from finished floor level), securely anchored into the structural RCC slab, complete with a stainless steel handrail, structural glass panels, heavy-duty base fixtures, and weather-resistant sealants as per specifications and direction of Engineer in Charge.	9.00	Rm.		

PROPOSED RESIDENTIAL BUILDING					
BILL OF QUANTITY - RESIDENTIAL BUILDING					
SI No.	Description of Work	Qty	Unit	Rate	Amount
L	Plumping Works (Inlet, Outlet, CP & Sanitary fittings for Toilets)				
	Ground floor - Bath Room	3.00	Nr.		
	Ground floor - Kitchen	1.00	Nr.		
	First floor - Bath Room	5.00	Nr.		
	First floor - Kitchen	2.00	Nr.		
	Second floor - Bath Room	5.00	Nr.		
	Second floor - Kitchen	2.00	Nr.		
	Terrace floor - Wash Room	2.00	Nr.		
	Terrace floor -Kitchen	1.00	Nr.		
M	Electrical Works				
	Stilt Floor	177.00	Sqm		
	First floor	190.00	Sqm		
	Second Floor	190.00	Sqm		
	Terrace Floor	105.00	Sqm		
	Total Amount				-