

PROPOSED RESIDENTIAL BUILDING															
SI No.	DESCRIPTION	NO'S	Length	Breadth	Depth	TOTAL QTY	Unit	REMARKS		Shuttering Qty					
			(m)	(m)	(m)					No's	L ength (ft)	Breadth (ft)	Depth (ft)	Qty (Sft)	Unit
A.	Sub Structure Works														
A.1	Site Clearance					220.00	Sqm								
	Plot Area	1.00	218.00			218.00									
A.2	Earth work Excavation					251.00	Cum								
	Footing F1	1.00	2.20	2.00	2.00	8.80									
	Footing F2	4.00	2.40	2.20	2.00	42.24									
	Footing F3	2.00	2.60	2.40	2.00	24.96									
	Footing F4	2.00	2.80	2.60	2.00	29.12									
	Footing F5	2.00	1.90	1.65	2.00	12.54									
	Footing F6	2.00	1.85	1.80	2.00	13.32									
	Footing F7	3.00	2.20	2.05	2.00	27.06									
	Footing F8	1.00	2.50	1.85	2.00	9.25									
	Footing F9	1.00	2.80	2.20	2.00	12.32									
	Footing F10	1.00	2.95	2.75	2.00	16.23									
	Footing F11	1.00	5.70	4.85	2.00	55.29									
A.3	Anti-termite treatment - I					126.00	Sqm								
	Footing F1	1.00	2.20	2.00		4.40									
	Footing F2	4.00	2.40	2.20		21.12									
	Footing F3	2.00	2.60	2.40		12.48									
	Footing F4	2.00	2.80	2.60		14.56									
	Footing LF1	2.00	1.90	1.65		6.27									
	Footing LF2	2.00	1.85	1.80		6.66									
	Footing LF3	3.00	2.20	2.05		13.53									
	Footing LF4	1.00	2.50	1.85		4.63									
	Footing LF5	1.00	2.80	2.20		6.16									
	Footing CF1	1.00	2.95	2.75		8.11									
	Footing CF2	1.00	5.70	4.85		27.65									
A.4	Road Base Filling-100mm Thk					13.00	Cum								
	Footing F1	1.00	2.20	2.00	0.10	0.44									
	Footing F2	4.00	2.40	2.20	0.10	2.11									
	Footing F3	2.00	2.60	2.40	0.10	1.25									
	Footing F4	2.00	2.80	2.60	0.10	1.46									
	Footing LF1	2.00	1.90	1.65	0.10	0.63									
	Footing LF2	2.00	1.85	1.80	0.10	0.67									
	Footing LF3	3.00	2.20	2.05	0.10	1.35									

PROPOSED RESIDENTIAL BUILDING															
			Length	Breadth	Depth			REMARKS		Shuttering Qty					
	Footing LF4	1.00	2.50	1.85	0.10	0.46									
	Footing LF5	1.00	2.80	2.20	0.10	0.62									
	Footing CF1	1.00	2.95	2.75	0.10	0.81									
	Footing CF2	1.00	5.70	4.85	0.10	2.76									
A.5	P.C.C Laying (1:4:8) -100mmThk					13.00	Cum								
	Footing F1	1.00	2.20	2.00	0.10	0.44									
	Footing F2	4.00	2.40	2.20	0.10	2.11									
	Footing F3	2.00	2.60	2.40	0.10	1.25									
	Footing F4	2.00	2.80	2.60	0.10	1.46									
	Footing LF1	2.00	1.90	1.65	0.10	0.63									
	Footing LF2	2.00	1.85	1.80	0.10	0.67									
	Footing LF3	3.00	2.20	2.05	0.10	1.35									
	Footing LF4	1.00	2.50	1.85	0.10	0.46									
	Footing LF5	1.00	2.80	2.20	0.10	0.62									
	Footing CF1	1.00	2.95	2.75	0.10	0.81									
	Footing CF2	1.00	5.70	4.85	0.10	2.76									
A.6	R.C.C - M30 & Fe500D - Footing Concrete					44.00	Cum						77.00	Sqm	1.75
	Footing F1	1.00	2.00	1.80	0.35	1.26			1.00	7.60		0.35	2.66		
	Footing F2	4.00	2.20	2.00	0.40	7.04			4.00	8.40		0.40	13.44		
	Footing F3	2.00	2.40	2.20	0.40	4.22			2.00	9.20		0.40	7.36		
	Footing F4	2.00	2.60	2.40	0.50	6.24			2.00	10.00		0.50	10.00		
	Footing LF1	2.00	1.70	1.45	0.40	1.97			2.00	6.30		0.40	5.04		
	Footing LF2	2.00	1.65	1.60	0.40	2.11			2.00	6.50		0.40	5.20		
	Footing LF3	3.00	2.00	1.85	0.40	4.44			3.00	7.70		0.40	9.24		
	Footing LF4	1.00	2.30	1.65	0.40	1.52			1.00	7.90		0.40	3.16		
	Footing LF5	1.00	2.60	2.00	0.45	2.34			1.00	9.20		0.45	4.14		
	Footing CF1	1.00	2.75	2.55	0.40	2.81			1.00	14.76		0.40	5.90		
	Footing CF2	1.00	5.50	4.65	0.40	10.23			1.00	27.85		0.40	11.14		
A.7	RCC Pedestal (M30 & Fe500D)					8.00	Cum						68.00	Sqm	8.50
	Column,C1	4.00	0.40	0.60	1.40	1.34			4.00	2.00		1.40	11.20		
	Column,C2	7.00	0.40	0.60	1.40	2.35			7.00	2.00		1.40	19.60		
	Column,C3	8.00	0.40	0.60	1.40	2.69			8.00	2.00		1.40	22.40		
	Column,C4	3.00	0.40	0.60	1.40	1.01			3.00	2.00		1.40	8.40		
	Column,C5	4.00	0.20	0.40	1.40	0.45			4.00	1.20		1.40	6.72		
A.8	R.C.C Lift Pit Wall (M30 & Fe500D)					2.00	Cum						14.00	Sqm	7.00
	Lift Pit Wall-200mm Thk	1.00	5.00	0.20	1.40	1.40			2.00	5.00		1.40	14.00		

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS	Shuttering Qty					
A.9	Earth filling (Available Earth)					173.00	Cum							
	Filling Qty - Excavated Area	1.00			251.00	251.00								
	D/F Sub Structure Qty	-1.00			78.00	-78.00								
B.	Super Structure Works - Above N.G.L							From N.G.L To G.F.L						
B.1	Earth work excavation-II (for Plinth Beam)					11.00	Cum							
	TB1,1a,2,3,3a,4,CTB1,2,3-230*500	1.00	127.50	0.43	0.20	10.97								
B.2	Ant termite treatment					55.00	Sqm							
	TB1,1a,2,3,3a,4,CTB1,2,3-230*500	1.00	127.50	0.43		54.83								
B.3	P.C.C Laying (1:4:8)-50mm Thk					3.00	Cum							
	TB1,1a,2,3,3a,4,CTB1,2,3-230*500	1.00	127.50	0.43	0.05	2.74								
B.5	R.C.C Tie Beam (M30 & Fe500D)					15.00	Cum					128.00	Sqm	8.53
	TB1,1a,2,3,3a,4,CTB1,2,3-230*500	1.00	127.50	0.23	0.50	14.66			2.00	127.50		0.50	128.00	
B.6	9" Thk-B.W -Basement					6.00	Cum					-	Sqm	Basement Plas
	BW @+0.6m Lvl	1.00	23.20	0.23	0.10	0.53								
	BW @+0.75m Lvl	1.00	92.50	0.23	0.25	5.32								
	BW @+0.75m & +0.6m Lvl	1.00	10.60	0.23	0.15	0.37								
B.7	RCC Column (M30 & Fe500D)					4.00	Cum	PB top to GB Top				37.00	Sqm	9.25
	Column,C1	4.00	0.40	0.60	0.75	0.72			4.00	2.00		0.75	6.00	
	Column,C2	7.00	0.40	0.60	0.75	1.26			7.00	2.00		0.75	10.50	
	Column,C3	8.00	0.40	0.60	0.75	1.44			8.00	2.00		0.75	12.00	
	Column,C4	3.00	0.40	0.60	0.75	0.54			3.00	2.00		0.75	4.50	
	Column,C5	4.00	0.20	0.40	0.75	0.24			4.00	1.20		0.75	3.60	
	Column,NC	1.00	0.23	0.23	3.00	0.16		NGL to +3.0m SSL	1.00	0.92		0.75	0.69	
B.8	Earth filling in Basement					77.00	Cum	From P.B Drawing						
	Filling area@ +0.75m lvl	1.00		98.50	0.60	59.10								
	Filling area@ +0.6m lvl	1.00		75.50	0.45	33.98								
	D/F Tie Beam	-1.00	33.80	0.23	0.45	-3.50								
	D/F Tie Beam	-1.00	92.50	0.23	0.60	-12.77								
B.9	Ant termite treatment					174.00	Sqm							
	Filling Area	1.00		174.00		174.00								
B.10	P.C.C Laying (1:2:4) -50mm Thk Flooring					7.00	Cum							
	Filling Area	1.00		174.00	0.05	8.70								
	D/F Tie Beam	-1.00	126.30	0.23	0.05	-1.45								

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS	Shuttering Qty					
B.11	Grade Slab (M30 & Fe500D)					14.00	Cum							
	Filling Area	1.00		174.00	0.10	17.40								
	D/F Tie Beam	-1.00	126.30	0.23	0.10	-2.90								
B.12	12mm Thk Flexible Sheet Laying-150mm Depth					128.00	Rm					13.00	Sqm	0.10
	Grade Slab	1.00	127.50			127.50			1.00	127.50		0.10	12.75	
B.13	Polyethelene Sheet Laying					209.00	Sqm							
	Grade Slab	1.00		144.95		144.95								
	Wall Portion	1.00	127.50		0.50	63.75								
C.	Super Structure Works - Ground floor													
C.1	R.C.C Column (M30 & Fe500D)					16.00	Cum					137.00	Sqm	8.56
	Column,C1	4.00	0.40	0.60	2.80	2.69			4.00	2.00		2.80	22.40	
	Column,C2	7.00	0.40	0.60	2.80	4.70			7.00	2.00		2.80	39.20	
	Column,C3	8.00	0.40	0.60	2.80	5.38			8.00	2.00		2.80	44.80	
	Column,C4	3.00	0.40	0.60	2.80	2.02			3.00	2.00		2.80	16.80	
	Column,C5	4.00	0.20	0.40	2.80	0.90			4.00	1.20		2.80	13.44	
C.2	230mm Thk -Brickwork					30.00	Cum							
	230mm Thk BW	1.00	53.00	0.23	2.80	34.13								
	D/F													
	Main Door MD1, (1100 X2100)	-1.00	1.20	0.23	2.10	-0.58								
	Door D1, (900 X2100)	-2.00	1.10	0.23	2.10	-1.06								
	Window W, (1800 X 1200)	-3.00	0.80	0.23	2.10	-1.16								
	Window W, (1500 X 1200)	-1.00	1.80	0.23	1.20	-0.50								
	Entrance Gate, EG (1200 X2100)	-1.00	1.20	0.23	2.10	-0.58								
	Ventilator V, (600 X 600)	-3.00	0.60	0.23	0.60	-0.25								
C.3	115mm Thk -Brickwork					89.00	Sqm							
	Inner Wall	1.00	34.30		2.80	96.04								
	Door D1, (900 X2100)	-1.00	1.10		2.10	-2.31								
	Door D2, (800 X 2100)	-3.00	0.80		2.10	-5.04								
C.4	RCC - Entrance Steps					3.00	Cum					10.00	Sqm	3.33
	Steps	1.00	1.20	0.30	0.15	0.05			1.00	1.20	0.45		0.54	
	Ramp	1.00	10.50	1.00	0.25	2.63			1.00	2.00		0.25	0.50	
									2.00	0.30		0.15	0.09	
C.6	R.C.C Platform & Loft (M30 & Fe500D)					1.00	Cum					9.00	Sqm	9.00
	Kitchen-Platform	1.00	4.30	0.61	0.10	0.26			1.00	4.30	0.71		3.05	
	M.Bed Room	1.00	2.90	0.61	0.10	0.18			1.00	2.90	0.71		2.06	
	Bed Room-1	1.00	3.00	0.61	0.10	0.18			1.00	3.00	0.71		2.13	
	Bed Room-2	1.00	2.25	0.61	0.10	0.14			1.00	2.25	0.71		1.60	
C.7	R.C.C Sill Beam (M30 & Fe500D)					2.00	Cum					17.00	Sqm	8.50

PROPOSED RESIDENTIAL BUILDING															
			Length	Breadth	Depth			REMARKS				Shuttering Qty			
	Sill Beam-230mm Thk BW	1.00	53.00	0.23	0.10	1.22			2.00	53.00		0.10	10.60	Side	
	Sill Beam-115mm Thk BW	1.00	34.30	0.12	0.10	0.39			2.00	34.30		0.10	6.86	Side	
C.8	R.C.C Lintel Beam (M30 & Fe500D)					4.00	Cum						43.00	Sqm	10.75
	Lintel Beam-230mm Thk BW	1.00	53.00	0.23	0.23	2.80			2.00	53.00		0.23	24.38	Side	
	Lintel Beam-115mm Thk BW	1.00	34.30	0.12	0.23	0.91			2.00	34.30		0.23	15.78	Side	
									1.00	10.60	0.23		2.44	Bottom	
									1.00	3.50	0.12		0.40	Bottom	
C.9	R.C.C Sunshade (M30 & Fe500D)					1.00	Cum						6.00	Sqm	6.00
	Window W, (1800 X 1200)	3.00	1.26	0.61	0.10	0.23			3.00	1.26	0.71		2.68	Side & Bottom	
	Window W, (1500 X 1200)	1.00	2.26	0.61	0.10	0.14			1.00	2.26	0.71		1.60	Side & Bottom	
	Ventilator V, (600 X 600)	2.00	1.06	0.61	0.10	0.13			2.00	1.06	0.71		1.50	Side & Bottom	
C.10	R.C.C Staircase (M30 & Fe500D)					2.00	Cum						14.00	Sqm	7.00
	Flight Slab-1	2.00	1.75	1.10	0.15	0.58			2.00	1.75	1.10		3.85	F.S-Bottom	
	Flight Slab-2	1.00	1.95	1.10	0.15	0.32			1.00	1.95	1.10		2.15	F.S-Bottom	
	Midlanding Slab-1	2.00	1.10	0.95	0.15	0.31			4.00	1.75		0.15	1.05	F.S-side	
	Midlanding Beam	1.00	4.63	0.23	0.50	0.53			2.00	1.10	0.95		2.09	Landing slab	
	Steps	22.00	1.10	0.30	0.15	0.54			22.00	1.10		0.15	3.63	Steps-Front	
									44.00		0.30	0.08	0.99	Steps-Side	
C.11	R.C.C Beam (M30 & Fe500D)					12.00	Cum						101.00	Sqm	8.42
	B1,1a,2,3,4,5	1.00	140.00	0.23	0.35	11.27			2.00	140.00		0.35	98.00		
	B1*	1.00	4.15	0.20	0.35	0.29			2.00	4.15		0.35	2.91		
C.12	R.C.C Slab (M30 & Fe500D)					28.00	Cum						196.00	Sqm	7.00
	S1 -150mm Thick	1.00	187.00		0.15	28.05			1.00	187.00			187.00	Bottom of slabs	
									1.00	56.00		0.15	8.40	Side	
									1.00	6.00		0.15	0.90	Side of Stair Area	
D.	Super Structure Works - First Floor							First Floor Level							
D.1	R.C.C Column					16.00	Cum						142.00	Sqm	8.88
	Column,C1	4.00	0.40	0.60	2.80	2.69			4.00	2.00		2.80	22.40		
	Column,C2	7.00	0.40	0.60	2.80	4.70			7.00	2.00		2.80	39.20		
	Column,C3	8.00	0.40	0.60	2.80	5.38			8.00	2.00		2.80	44.80		
	Column,C4	3.00	0.40	0.60	2.80	2.02			3.00	2.00		2.80	16.80		
	Column,C5	4.00	0.20	0.40	2.80	0.90			4.00	1.20		2.80	13.44		
	Column, FC	2.00	0.23	0.23	2.80	0.30			2.00	0.92		2.80	5.15		
D.2	230mm Thk -Brickwork					44.00	Cum								
	Wall-230mm Thk	1.00	84.00	0.23	2.80	54.10									
	D/F														
	Main Door MD1, (1100 X2100)	-1.00	1.10	0.23	2.10	-0.53									
	Main Door MD2, (1050 X2100)	-1.00	1.05	0.23	2.10	-0.51									
	Door D1, (900 X2100)	-6.00	0.90	0.23	2.10	-2.61									
	Window W, (1800 X 1200)	-8.00	1.80	0.23	1.20	-3.97									
	Window W, (1500 X 1200)	-1.00	1.50	0.23	1.20	-0.41									

PROPOSED RESIDENTIAL BUILDING															
			Length	Breadth	Depth			REMARKS				Shuttering Qty			
	Window W, (1100 X 1200)	-2.00	1.10	0.23	1.20	-0.61									
	Ventilator V, (600 X 600)	-5.00	0.60	0.23	0.60	-0.41									
	Sliding Door SD, (2000 X 2100)	-1.00	2.00	0.23	2.10	-0.97									
	Open	-1.00	0.60	0.23	2.10	-0.29									
D.3	115mm Thk -Brickwork					106.00	Sqm								
	Wall	1.00	40.75		2.80	114.10									
	D/F														
	Door D2, (800 X 2100)	-5.00	0.80		2.10	-8.40									
D.4	R.C.C Platform & Loft (M30 & Fe500D)					2.00	Cum						18.00	Sqm	9.00
	Kitchen Platform	1.00	9.00	0.61	0.08	0.44			1.00	9.00	0.69		6.21		
	MB-Loft	1.00	5.80	0.61	0.08	0.28			1.00	5.80	0.69		4.00		
	BR1-Loft	1.00	6.00	0.61	0.08	0.29			1.00	6.00	0.69		4.14		
	BR2-Loft	1.00	4.70	0.61	0.08	0.23			1.00	4.70	0.69		3.24		
D.5	R.C.C Sill Beam (M30 & Fe500D)					3.00	Cum						25.00	Sqm	8.33
	Sill Beam-230mm Thk BW	1.00	84.00	0.23	0.10	1.93			2.00	84.00		0.10	16.80	Side	
	Sill Beam-115mm Thk BW	1.00	40.75	0.12	0.10	0.47			2.00	40.75		0.10	8.15	Side	
D.6	R.C.C Lintel Beam (M30 & Fe500D)					6.00	Cum						65.00	Sqm	10.83
	Lintel Beam-230mm Thk BW	1.00	84.00	0.23	0.23	4.44			2.00	84.00		0.23	38.64	Side	
	Lintel Beam-115mm Thk BW	1.00	40.75	0.12	0.23	1.08			2.00	40.75		0.23	18.75	Side	
									1.00	31.25	0.23		7.19	Bottom	
									1.00	4.00	0.12		0.46	Bottom	
D.7	R.C.C Sunshade (M30 & Fe500D)					1.00	Cum						13.00	Sqm	13.00
	Window W, (1800 X 1200)	5.00	2.26	0.61	0.10	0.69			5.00	2.26	0.71		8.02	Side	
	Window W, (1500 X 1200)	1.00	1.96	0.61	0.10	0.12			1.00	1.96	0.71		1.39	Side	
	Ventilator V, (600 X 600)	2.00	1.06	0.61	0.10	0.13			2.00	1.06	0.71		1.50	Side	
	Ventilator V, (600 X 600)	1.00	2.25	0.61	0.10	0.14			1.00	2.25	0.71		1.60	Side	
D.8	R.C.C Beam (M30 & Fe500D)					12.00	Cum						101.00	Sqm	8.42
	B1,1a,2,3,4,5	1.00	140.00	0.23	0.35	11.27			2.00	140.00		0.35	98.00		
	B1*	1.00	4.15	0.20	0.35	0.29			2.00	4.15		0.35	2.91		
D.9	R.C.C Slab (M30 & Fe500D)					28.00	Cum						196.00	Sqm	7.00
	S1 -150mm Thick	1.00	187.00		0.15	28.05			1.00	187.00			187.00	Bottom of slabs	
									1.00	56.00		0.15	8.40	Side	
									1.00	6.00		0.15	0.90	Side of Stair Area	
E.	Super Structure Works - Second Floor							Second Floor Level							
E.1	R.C.C Column					16.00	Cum						142.00	Sqm	8.88
	Column,C1	4.00	0.40	0.60	2.80	2.69			4.00	2.00		2.80	22.40		
	Column,C2	7.00	0.40	0.60	2.80	4.70			7.00	2.00		2.80	39.20		
	Column,C3	8.00	0.40	0.60	2.80	5.38			8.00	2.00		2.80	44.80		
	Column,C4	3.00	0.40	0.60	2.80	2.02			3.00	2.00		2.80	16.80		

PROPOSED RESIDENTIAL BUILDING																	
			Length	Breadth	Depth			REMARKS			Shuttering Qty						
	Column, C5	4.00	0.20	0.40	2.80	0.90				4.00	1.20		2.80	13.44			
	Column, FC	2.00	0.23	0.23	2.80	0.30				2.00	0.92		2.80	5.15			
E.2	230mm Thk -Brickwork					44.00	Cum										
	Wall-230mm Thk	1.00	84.00	0.23	2.80	54.10											
	D/F																
	Main Door MD1, (1100 X2100)	-1.00	1.10	0.23	2.10	-0.53											
	Main Door MD2, (1050 X2100)	-1.00	1.05	0.23	2.10	-0.51											
	Door D1, (900 X2100)	-6.00	0.90	0.23	2.10	-2.61											
	Window W, (1800 X 1200)	-8.00	1.80	0.23	1.20	-3.97											
	Window W, (1500 X 1200)	-1.00	1.50	0.23	1.20	-0.41											
	Window W, (1100 X 1200)	-2.00	1.10	0.23	1.20	-0.61											
	Ventilator V, (600 X 600)	-5.00	0.60	0.23	0.60	-0.41											
	Sliding Door SD, (2000 X 2100)	-1.00	2.00	0.23	2.10	-0.97											
	Open	-1.00	0.60	0.23	2.10	-0.29											
E.3	115mm Thk -Brickwork					106.00	Sqm										
	Wall	1.00	40.75		2.80	114.10											
	D/F																
	Door D2, (800 X 2100)	-5.00	0.80		2.10	-8.40											
E.4	R.C.C Platform & Loft (M30 & Fe500D)					2.00	Cum							18.00	Sqm	9.00	
	Kitchen Platform	1.00	9.00	0.61	0.08	0.44			1.00	9.00	0.69			6.21			
	MB-Loft	1.00	5.80	0.61	0.08	0.28			1.00	5.80	0.69			4.00			
	BR1-Loft	1.00	6.00	0.61	0.08	0.29			1.00	6.00	0.69			4.14			
	BR2-Loft	1.00	4.70	0.61	0.08	0.23			1.00	4.70	0.69			3.24			
E.5	R.C.C Sill Beam (M30 & Fe500D)					3.00	Cum							25.00	Sqm	8.33	
	Sill Beam-230mm Thk BW	1.00	84.00	0.23	0.10	1.93			2.00	84.00		0.10		16.80	Side		
	Sill Beam-115mm Thk BW	1.00	40.75	0.12	0.10	0.47			2.00	40.75		0.10		8.15	Side		
E.6	R.C.C Lintel Beam (M30 & Fe500D)					6.00	Cum							65.00	Sqm	10.83	
	Lintel Beam-230mm Thk BW	1.00	84.00	0.23	0.23	4.44			2.00	84.00		0.23		38.64	Side		
	Lintel Beam-115mm Thk BW	1.00	40.75	0.12	0.23	1.08			2.00	40.75		0.23		18.75	Side		
									1.00	31.25	0.23			7.19	Bottom		
									1.00	4.00	0.12			0.46	Bottom		
E.7	R.C.C Sunshade (M30 & Fe500D)					1.00	Cum							13.00	Sqm	13.00	
	Window W, (1800 X 1200)	5.00	2.26	0.61	0.10	0.69			5.00	2.26	0.71			8.02	Side		
	Window W, (1500 X 1200)	1.00	1.96	0.61	0.10	0.12			1.00	1.96	0.71			1.39	Side		
	Ventilator V, (600 X 600)	2.00	1.06	0.61	0.10	0.13			2.00	1.06	0.71			1.50	Side		
	Ventilator V, (600 X 600)	1.00	2.25	0.61	0.10	0.14			1.00	2.25	0.71			1.60	Side		
E.8	R.C.C Beam (M30 & Fe500D)					11.00	Cum							94.00	Sqm	8.55	
	B1,1a,2,3,4,5	1.00	130.00	0.23	0.35	10.47			2.00	130.00		0.35		91.00			
	B1*	1.00	4.15	0.20	0.35	0.29			2.00	4.15		0.35		2.91			

PROPOSED RESIDENTIAL BUILDING															
			Length	Breadth	Depth			REMARKS	Shuttering Qty						
E.9	R.C.C Slab (M30 & Fe500D)					28.00	Cum						196.00	Sqm	7.00
	S1 -150mm Thick	1.00	187.00		0.15	28.05			1.00	187.00			187.00	Bottom of slabs	
									1.00	56.00		0.15	8.40	Side	
									1.00	6.00		0.15	0.90	Side of Stair Area	
F	Super Structure Works - Terrace Floor														
F.1	R.C.C Column (M30 & Fe500D)					13.00	Cum						115.00	Sqm	8.85
	Column,C1	2.00	0.40	0.60	2.80	1.34			2.00	2.00		2.80	11.20		
	Column,C1	2.00	0.40	0.60	1.15	0.55			2.00	2.00		1.15	4.60		
	Column,C2	5.00	0.40	0.60	2.80	3.36			5.00	2.00		2.80	28.00		
	Column,C2	2.00	0.40	0.60	1.15	0.55			2.00	2.00		1.15	4.60		
	Column,C3	4.00	0.40	0.60	2.80	2.69			4.00	2.00		2.80	22.40		
	Column,C3	4.00	0.40	0.60	1.15	1.10			4.00	2.00		1.15	9.20		
	Column,C4	3.00	0.40	0.60	2.80	2.02			3.00	2.00		2.80	16.80		
	Column,C5	4.00	0.20	0.40	2.80	0.90			4.00	1.20		2.80	13.44		
	Column, FC	2.00	0.23	0.23	2.80	0.30			2.00	0.92		2.80	5.15		
F.2	230mm Thk -Brickwork					48.00	Cum								
	Wall-230thk BW	1.00	55.00	0.23	2.80	35.42									
	D/F														
	Main Door MD1, (1100 X2100)	-1.00	1.10	0.23	2.10	-0.53									
	Main Door MD2, (1050 X2100)	-1.00	1.05	0.23	2.10	-0.51									
	Door D1, (900 X2100)	-3.00	0.90	0.23	2.10	-1.30									
	Window W, (1800 X 1200)	-4.00	1.80	0.23	1.20	-1.99									
	Window W, (1100 X 1200)	-2.00	1.10	0.23	1.20	-0.61									
	Ventilator V, (600 X 600)	-3.00	0.60	0.23	0.60	-0.25									
	Sliding Door SD, (2000 X 2100)	-1.00	2.00	0.23	2.10	-0.97									
	Parapet Wall	1.00	24.00	0.23	1.15	6.35									
	Parapet Wall-Upper Roof	1.00	45.00	0.23	1.15	11.90									
F.3	115mm Thk -Brickwork					53.00	Sqm								
	Wall	1.00	20.25		2.80	56.70									
	D/F														
	Door D2, (800 X 2100)	-2.00	0.80		2.10	-3.36									
F.4	R.C.C Platform & Loft (M30 & Fe500D)					1.00	Cum						9.00	Sqm	9.00
	Kitchen Platform	1.00	4.70	0.61	0.08	0.23			1.00	4.70	0.69		3.24		
	MB-Loft	1.00	2.90	0.61	0.08	0.14			1.00	2.90	0.69		2.00		
	BR1-Loft	1.00	2.45	0.61	0.08	0.12			1.00	2.45	0.69		1.69		
	BR2-Loft	1.00	2.55	0.61	0.08	0.12			1.00	2.55	0.69		1.76		
F.5	R.C.C Sill Beam (M30 & Fe500D)					2.00	Cum						15.00	Sqm	7.50
	Sill Beam-230mm Thk BW	1.00	55.00	0.23	0.10	1.27			2.00	55.00		0.10	11.00	Side	
	Sill Beam-115mm Thk BW	1.00	20.25	0.12	0.10	0.23			2.00	20.25		0.10	4.05	Side	

PROPOSED RESIDENTIAL BUILDING																			
			Length	Breadth	Depth			REMARKS		Shuttering Qty									
F.6	R.C.C Lintel Beam (M30 & Fe500D)					3.00	Cum							39.00	Sqm	13.00			
	Lintel Beam-230mm Thk BW	1.00	55.00	0.23	0.23	2.91			2.00	55.00		0.23	25.30	Side					
	Lintel Beam-115mm Thk BW	1.00	20.25	0.12	0.23	0.54			2.00	20.25		0.23	9.32	Side					
									1.00	18.05	0.23		4.15	Bottom					
									1.00	1.60	0.12		0.18	Bottom					
F.7	R.C.C Sunshade (M30 & Fe500D)					1.00	Cum						5.00	Sqm	5.00				
	Window W, (1800 X 1200)	2.00	2.26	0.61	0.10	0.28			2.00	2.26	0.71		3.21	Side					
	Ventilator V, (600 X 600)	1.00	2.25	0.61	0.10	0.14			1.00	2.25	0.71		1.60	Side					
F.8	R.C.C Beam (M30 & Fe500D)					7.00	Cum						61.00	Sqm	8.71				
	B1,1a,2,3,4,5	1.00	81.00	0.23	0.35	6.52			2.00	81.00		0.35	56.70						
	B1*	1.00	6.60	0.20	0.35	0.46			2.00	6.60		0.35	4.62						
F.9	R.C.C Slab (M30 & Fe500D)					17.00	Cum						117.00	Sqm	6.88				
	S1 -150mm Thick including Lift Room	1.00		110.00	0.15	16.50			1.00	110.00			110.00	Bottom of slabs					
									1.00	45.00		0.15	6.75	Side					
F	Finishing Works												Flooring Works						
F.1	Ceiling Plastering												Vitrified T	Anti Skid T	Wall Tiles	Staircase	Kitchen Platfo	Carparki	Water Proofin
	Ground Floor					155.00	Sqm						68.00	8.00	50.00	13.00	6.00	72.00	8.00
	Master Bed Room	1.00	2.97	3.36		9.98			9.98										
	Master Bed Room-Passage	1.00	0.90	1.83		1.65			1.65										
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71				2.71	19.28							2.71	
	Kitchen	1.00	3.57	2.10		7.50			7.50					5.16					
	Bed Room-1	1.00	3.26	3.01		9.81			9.81										
	Bed Room-1 Toilet	1.00	2.13	1.20		2.56				2.56	18.46							2.56	
	Bed Room-2	1.00		9.15		9.15			9.15										
	Bed Room-2 Toilet	1.00		2.30		2.30				2.30	11.97							2.30	
	Living Cum Dining	1.00		24.00		24.00			24.00										
	Entrance Passage	1.00	1.30	4.15		5.40			5.40										
	Flight Slab-1,3	2.00	1.75	1.10		3.85													
	Flight Slab-2	1.00	1.95	1.10		2.15													
	Landing Slab	2.00	0.90	1.10		1.98						1.98							
	Parking	1.00		71.50		71.50											71.50		
	Steps-Tread											7.26							
	Steps-Riser											3.63							
	First Floor					155.00	Sqm						131.00	17.00	89.00	13.00	11.00	-	13.00
	Flat -MD1																		
	Master Bed Room	1.00	2.97	3.36		9.98			9.98										
	Master Bed Room-Passage	1.00	0.90	1.83		1.65			1.65										
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71				2.71	19.28							2.71	
	Kitchen	1.00	3.57	2.10		7.50			7.50					5.74					
	Bed Room-1	1.00	3.26	3.01		9.81			9.81										
	Bed Room-1 Toilet	1.00	2.13	1.20		2.56				2.56	18.46							2.56	

PROPOSED RESIDENTIAL BUILDING																
			Length	Breadth	Depth			REMARKS		Shuttering Qty						
	Bed Room-2	1.00	9.15			9.15			9.15							
	Bed Room-2 Toilet	1.00	2.30			2.30				2.30	11.97				2.30	
	Living Cum Dining	1.00	24.00			24.00			24.00							
	Entrance Passage	1.00	1.30	4.15		5.40			5.40							
	Flat -MD2															
	Master Bed Room	1.00	3.22	2.95		9.50			9.50							
	Master Bed Room-Passage	1.00	0.98	1.17		1.15			1.15							
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71				2.71	19.28				2.71	
	Kitchen	1.00	3.93	2.17		8.53			8.53				5.16			
	Bed Room-1	1.00	3.33	2.55		8.49			8.49							
	Bed Room-1 Toilet	1.00	2.26	1.20		2.71				2.71	19.28				2.71	
	Bed Room-2	1.00	2.71	2.55		6.91			6.91							
	Living Cum Dining	1.00	28.50			28.50			28.50							
	Balcony	1.00	2.71	1.25		3.39				3.39						
	Flight Slab-1,3	2.00	1.75	1.10		3.85										
	Flight Slab-2	1.00	1.95	1.10		2.15										
	Landing Slab	2.00	0.90	1.10		1.98						1.98				
	Steps-Tread											7.26				
	Steps-Riser											3.63				
	Second Floor					155.00	Sqm		131.00	17.00	89.00	13.00	11.00	-	13.00	
	Flat -MD1															
	Master Bed Room	1.00	2.97	3.36		9.98			9.98							
	Master Bed Room-Passage	1.00	0.90	1.83		1.65			1.65							
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71				2.71	19.28				2.71	
	Kitchen	1.00	3.57	2.10		7.50			7.50				5.74			
	Bed Room-1	1.00	3.26	3.01		9.81			9.81							
	Bed Room-1 Toilet	1.00	2.13	1.20		2.56				2.56	18.46				2.56	
	Bed Room-2	1.00	9.15			9.15			9.15							
	Bed Room-2 Toilet	1.00	2.30			2.30				2.30	11.97				2.30	
	Living Cum Dining	1.00	24.00			24.00			24.00							
	Entrance Passage	1.00	1.30	4.15		5.40			5.40							
	Flat -MD2															
	Master Bed Room	1.00	3.22	2.95		9.50			9.50							
	Master Bed Room-Passage	1.00	0.98	1.17		1.15			1.15							
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71				2.71	19.28				2.71	
	Kitchen	1.00	3.93	2.17		8.53			8.53				5.16			
	Bed Room-1	1.00	3.33	2.55		8.49			8.49							
	Bed Room-1 Toilet	1.00	2.26	1.20		2.71				2.71	19.28				2.71	
	Bed Room-2	1.00	2.71	2.55		6.91			6.91							
	Living Cum Dining	1.00	28.50			28.50			28.50							
	Balcony	1.00	2.71	1.25		3.39				3.39						
	Flight Slab-1,3	2.00	1.75	1.10		3.85										
	Flight Slab-2	1.00	1.95	1.10		2.15										
	Landing Slab	2.00	0.90	1.10		1.98						1.98				
	Steps-Tread											7.26				

PROPOSED RESIDENTIAL BUILDING																
			Length	Breadth	Depth			REMARKS		Shuttering Qty						
	Steps-Riser												3.63			
	Terrace Floor					90.00	Sqm			82.00	9.00	39.00	-	6.00	-	6.00
	Flat -MD2															
	Master Bed Room	1.00	3.22	2.95		9.50				9.50						
	Master Bed Room-Passage	1.00	0.98	1.17		1.15				1.15						
	Master Bed Room-Toilet	1.00	2.26	1.20		2.71					2.71	19.28				2.71
	Kitchen	1.00	3.93	2.17		8.53				8.53				5.64		
	Bed Room-1	1.00	3.33	2.55		8.49				8.49						
	Bed Room-1 Toilet	1.00	2.26	1.20		2.71					2.71	19.28				2.71
	Bed Room-2	1.00	2.71	2.55		6.91				6.91						
	Living Cum Dining	1.00		28.50		28.50				28.50						
	Balcony	1.00	2.71	1.25		3.39					3.39					
	Entrance passage-(Lift & Stair Portion)	1.00	4.40	4.17		18.35				18.35						
										Skirting Works						
H.2	Internal Plastering					496.00	Sqm			Vitrified T	Anti Skid Ti	Lift Facia	Staircase	Parking Tile	Water Proofing	
	Ground Floor									95.00	-	3.00	11.00	7.00	4.00	
	Master Bed Room	1.00	12.66		3.15	39.88				12.66						
	Master Bed Room-Passage	1.00	4.56		3.15	14.36				4.56						
	Master Bed Room-Toilet	1.00	6.92		3.15	21.80				6.92						
	Kitchen	1.00	11.34		3.15	35.72				11.34						
	Bed Room-1	1.00	12.54		3.15	39.50				12.54						
	Bed Room-1 Toilet	1.00	6.66		3.15	20.98									2.00	
	Bed Room-2	1.00	12.50		3.15	39.38				12.50						
	Bed Room-2 Toilet	1.00	6.30		3.15	19.85									1.89	
	Living Cum Dining	1.00	26.00		3.15	81.90				26.00						
	Entrance Passage cum Stair	1.00	16.34		3.30	53.92				16.34			10.35			
	Lift Wall	1.00	7.50		3.30	24.75						2.31				
	Parking-Int.Wall Plastering	1.00	28.60		3.15	90.09										
	Column Plastering,C3	3.00	1.66		3.15	15.69								4.98		
	Column Plastering,C4	1.00	1.66		3.15	5.23								1.66		
	Kitchen Platform plastering	1.00	4.30		1.30	5.59										
	Bed Room Plastering	1.00	8.15		1.30	10.60										
	D/F															
	Entrance Gate, EG (1200 X2100)	-1.00	1.20		2.10	-2.52				-1.20						
	Main Door MD1, (1100 X2100)	-2.00	1.10		2.10	-4.62				-2.20						
	Door D1, (900 X2100)	-6.00	0.90		2.10	-11.34				-5.40						
	Door D2, (800 X 2100)	-6.00	0.80		2.10	-10.08										
	Window W, (1800 X 1200)	-4.00	1.80		1.20	-8.64										
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80										
	Ventilator V, (600 X 600)	-3.00	0.60		0.60	-1.08										
	Jams Plastering															
	Entrance Gate, EG (1200 X2100)	1.00	5.40		0.23	1.24										
	Main Door MD1, (1100 X2100)	1.00	5.30		0.23	1.22										
	Door D1, (900 X2100)	3.00	5.10		0.23	3.52										
	Door D2, (800 X 2100)	3.00	5.00		0.12	1.73										

PROPOSED RESIDENTIAL BUILDING															
			Length	Breadth	Depth			REMARKS		Shuttering Qty					
	Window W, (1800 X 1200)	4.00	6.00		0.23	5.52									
	Window W, (1500 X 1200)	1.00	5.40		0.23	1.24									
	Ventilator V, (600 X 600)	3.00	2.40		0.23	1.66									
	First Floor					643.00	Sqm			138.00	-	3.00	11.00	-	11.00
	Flat -MD1														
	Master Bed Room	1.00	12.66		3.15	39.88				12.66					
	Master Bed Room-Passage	1.00	5.46		3.15	17.20				5.46					
	Master Bed Room-Toilet	1.00	6.92		3.15	21.80								2.08	
	Kitchen	1.00	11.34		3.15	35.72				11.34					
	Bed Room-1	1.00	12.54		3.15	39.50				12.54					
	Bed Room-1 Toilet	1.00	6.66		3.15	20.98								2.00	
	Bed Room-2	1.00	12.50		3.15	39.38				12.50					
	Bed Room-2 Toilet	1.00	6.30		3.15	19.85								1.89	
	Living Cum Dining	1.00	26.00		3.15	81.90				26.00					
	Entrance Passage cum Stair	1.00	16.34		3.30	53.92				16.34			10.35		
	Lift Wall	1.00	7.50		3.30	24.75						2.31			
	Flat -MD2														
	Master Bed Room-Passage	1.00	12.34		3.15	38.87				12.34					
	Master Bed Room-Toilet	1.00	4.30		3.15	13.55								1.29	
	Kitchen	1.00	6.92		3.15	21.80				6.92					
	Bed Room-1	1.00	12.20		3.15	38.43				12.20					
	Bed Room-1 Toilet	1.00	11.76		3.15	37.04								3.53	
	Bed Room-2	1.00	6.92		3.15	21.80				6.92					
	Living Cum Dining	1.00	28.20		3.15	88.83				28.20					
	Kitchen Platform Plastering	1.00	9.00		1.30	11.70									
	Loft Plastering	1.00	16.50		1.30	21.45									
	D/F														
	Main Door MD1, (1100 X2100)	-2.00	1.10		2.10	-4.62				-2.20					
	Main Door MD2, (1050 X2100)	-2.00	1.05		2.10	-4.41				-2.10					
	Door D1, (900 X2100)	-12.00	0.90		2.10	-22.68				-10.80					
	Door D2, (800 X 2100)	-10.00	0.80		2.10	-16.80				-8.00					
	Window W, (1800 X 1200)	-8.00	1.80		1.20	-17.28									
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80									
	Window W, (1100 X 1200)	-2.00	1.10		1.20	-2.64									
	Ventilator V, (600 X 600)	-5.00	0.60		0.60	-1.80									
	Sliding Door SD, (2000 X 2100)	-1.00	2.00		2.10	-4.20				-2.00					
	Open	-2.00	0.61		2.10	-2.56				-1.22					
	Jams Plastering														
	Main Door MD1, (1100 X2100)	1.00	5.30		0.23	1.22									
	Main Door MD2, (1050 X2100)	1.00	5.25		0.23	1.21									
	Door D1, (900 X2100)	6.00	5.10		0.23	7.04									
	Door D2, (800 X 2100)	5.00	5.00		0.12	2.88									
	Window W, (1800 X 1200)	8.00	6.00		0.23	11.04									
	Window W, (1500 X 1200)	1.00	4.20		0.23	0.97									

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS		Shuttering Qty				
	Window W, (1100 X 1200)	2.00	3.90		0.23	1.79								
	Ventilator V, (600 X 600)	5.00	3.50		0.23	4.03								
	Sliding Door SD, (2000 X 2100)	1.00	1.80		0.23	0.41								
	Open	2.00	6.20		0.23	2.85								
	Second Floor					643.00	Sqm		138.00	-	3.00	11.00	-	11.00
	Flat -MD1													
	Master Bed Room	1.00	12.66		3.15	39.88			12.66					
	Master Bed Room-Passage	1.00	5.46		3.15	17.20			5.46					
	Master Bed Room-Toilet	1.00	6.92		3.15	21.80								2.08
	Kitchen	1.00	11.34		3.15	35.72			11.34					
	Bed Room-1	1.00	12.54		3.15	39.50			12.54					
	Bed Room-1 Toilet	1.00	6.66		3.15	20.98								2.00
	Bed Room-2	1.00	12.50		3.15	39.38			12.50					
	Bed Room-2 Toilet	1.00	6.30		3.15	19.85								1.89
	Living Cum Dining	1.00	26.00		3.15	81.90			26.00					
	Entrance Passage cum Stair	1.00	16.34		3.30	53.92			16.34			10.35		
	Lift Wall	1.00	7.50		3.30	24.75					2.31			
	Flat -MD2													
	Master Bed Room-Passage	1.00	12.34		3.15	38.87			12.34					
	Master Bed Room-Toilet	1.00	4.30		3.15	13.55								1.29
	Kitchen	1.00	6.92		3.15	21.80			6.92					
	Bed Room-1	1.00	12.20		3.15	38.43			12.20					
	Bed Room-1 Toilet	1.00	11.76		3.15	37.04								3.53
	Bed Room-2	1.00	6.92		3.15	21.80			6.92					
	Living Cum Dining	1.00	28.20		3.15	88.83			28.20					
	Kitchen Platform Plastering	1.00	9.00		1.30	11.70								
	Loft Plastering	1.00	16.50		1.30	21.45								
	D/F													
	Main Door MD1, (1100 X2100)	-2.00	1.10		2.10	-4.62			-2.20					
	Main Door MD2, (1050 X2100)	-2.00	1.05		2.10	-4.41			-2.10					
	Door D1, (900 X2100)	-12.00	0.90		2.10	-22.68			-10.80					
	Door D2, (800 X 2100)	-10.00	0.80		2.10	-16.80			-8.00					
	Window W, (1800 X 1200)	-8.00	1.80		1.20	-17.28								
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80								
	Window W, (1100 X 1200)	-2.00	1.10		1.20	-2.64								
	Ventilator V, (600 X 600)	-5.00	0.60		0.60	-1.80								
	Sliding Door SD, (2000 X 2100)	-1.00	2.00		2.10	-4.20			-2.00					
	Open	-2.00	0.61		2.10	-2.56			-1.22					
	Jams Plastering													
	Main Door MD1, (1100 X2100)	1.00	5.30		0.23	1.22								
	Main Door MD2, (1050 X2100)	1.00	5.25		0.23	1.21								
	Door D1, (900 X2100)	6.00	5.10		0.23	7.04								
	Door D2, (800 X 2100)	5.00	5.00		0.12	2.88								
	Window W, (1800 X 1200)	8.00	6.00		0.23	11.04								
	Window W, (1500 X 1200)	1.00	4.20		0.23	0.97								

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS		Shuttering Qty				
	Window W, (1100 X 1200)	2.00	3.90		0.23	1.79								
	Ventilator V, (600 X 600)	5.00	3.50		0.23	4.03								
	Sliding Door SD, (2000 X 2100)	1.00	1.80		0.23	0.41								
	Open	2.00	6.20		0.23	2.85								
	Terrace Floor					371.00	Sqm			80.00	-	3.00	-	5.00
	Master Bed Room	1.00	12.34		3.15	38.87				12.34				
	Master Bed Room-Passage	1.00	3.32		3.15	10.46				3.32				
	Master Bed Room-Toilet	1.00	6.92		3.15	21.80								2.08
	Kitchen	1.00	12.20		3.15	38.43				12.20				
	Bed Room-1	1.00	11.76		3.15	37.04				11.76				
	Bed Room-1 Toilet	1.00	6.92		3.15	21.80								2.08
	Bed Room-2	1.00	10.52		3.15	33.14				10.52				
	Living Cum Dining	1.00	28.20		3.15	88.83				28.20				
	Entrance passage-(Lift & Stair Portion)	1.00	16.34		3.30	53.92				16.34				
	Lift Wall	1.00	7.50		4.50	33.75					2.31			
	Platform Plastering	1.00	4.70		1.28	6.02								
	Loft Plastering	1.00	7.90		1.28	10.11								
	D/F													
	Main Door MD1, (1100 X2100)	-1.00	1.10		2.10	-2.31				-1.10				
	Main Door MD2, (1050 X2100)	-2.00	1.05		2.10	-4.41				-2.10				
	Door D1, (900 X2100)	-6.00	0.90		2.10	-11.34				-5.40				
	Door D2, (800 X 2100)	-4.00	0.80		2.10	-6.72				-3.20				
	Window W, (1800 X 1200)	-4.00	1.80		1.20	-8.64								
	Window W, (1100 X 1200)	-2.00	1.10		1.20	-2.64								
	Ventilator V, (600 X 600)	-3.00	0.60		0.60	-1.08								
	Sliding Door SD, (2000 X 2100)	-1.00	2.00		2.10	-4.20				-2.00				
	Open	-2.00	0.60		2.10	-2.52				-1.20				
	Jams Plastering													
	Main Door MD1, (1100 X2100)	1.00	5.30		0.23	1.22								
	Main Door MD2, (1050 X2100)	1.00	5.25		0.23	1.21								
	Door D1, (900 X2100)	3.00	5.10		0.23	3.52								
	Door D2, (800 X 2100)	2.00	5.00		0.12	1.15								
	Window W, (1800 X 1200)	4.00	6.00		0.23	5.52								
	Window W, (1100 X 1200)	2.00	4.60		0.23	2.12								
	Ventilator V, (600 X 600)	3.00	2.40		0.23	1.66								
	Sliding Door SD, (2000 X 2100)	1.00	8.20		0.23	1.89								
	Open	2.00	5.40		0.23	2.48								
H.3	External Plastering													
	Ground Floor					168.00	Sqm							
	External wall	1.00	44.30		3.80	168.34								
	D/F													
	Window W, (1800 X 1200)	-4.00	1.80		1.20	-8.64								
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80								
	Ventilator V, (600 X 600)	-3.00	0.60		0.60	-1.08								

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS		Shuttering Qty				
	Sunshade Plastering													
	Window W, (1800 X 1200)	3.00	1.26		1.31	4.95								
	Window W, (1500 X 1200)	1.00	2.26		1.31	2.96								
	Ventilator V, (600 X 600)	2.00	1.06		1.31	2.78								
	First Floor					194.00	Sqm							
	Ext Wall	1.00	60.00		3.30	198.00								
	D/F													
	Window W, (1800 X 1200)	-8.00	1.80		1.20	-17.28								
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80								
	Window W, (1100 X 1200)	-2.00	1.10		1.20	-2.64								
	Ventilator V, (600 X 600)	-5.00	0.60		0.60	-1.80								
	Sliding Door SD, (2000 X 2100)	-1.00	2.00		2.10	-4.20								
	Sunshade Plastering													
	Window W, (1800 X 1200)	5.00	2.26		1.31	14.80								
	Window W, (1500 X 1200)	1.00	1.96		1.31	2.57								
	Ventilator V, (600 X 600)	2.00	1.06		1.31	2.78								
	Ventilator V, (600 X 600)	1.00	2.25		1.31	2.95								
	Second Floor					194.00	Sqm							
	Ext Wall	1.00	60.00		3.30	198.00								
	D/F													
	Window W, (1800 X 1200)	-8.00	1.80		1.20	-17.28								
	Window W, (1500 X 1200)	-1.00	1.50		1.20	-1.80								
	Window W, (1100 X 1200)	-2.00	1.10		1.20	-2.64								
	Ventilator V, (600 X 600)	-5.00	0.60		0.60	-1.80								
	Sliding Door SD, (2000 X 2100)	-1.00	2.00		2.10	-4.20								
	Sunshade Plastering													
	Window W, (1800 X 1200)	5.00	2.26		1.31	14.80								
	Window W, (1500 X 1200)	1.00	1.96		1.31	2.57								
	Ventilator V, (600 X 600)	2.00	1.06		1.31	2.78								
	Ventilator V, (600 X 600)	1.00	2.25		1.31	2.95								
	Terrace Floor					316.00								
	Terrace Floor	1.00	45.00		3.30	148.50								
	Parapet wall Plastering	1.00	24.00		2.53	60.72								
	Upper Parapet wall Plastering	1.00	45.00		2.53	113.85								
	D/F													
	Window W, (1800 X 1200)	-4.00	1.80		1.20	-8.64								
	Window W, (1100 X 1200)	-2.00	1.50		1.20	-3.60								
	Ventilator V, (600 X 600)	-3.00	1.10		1.20	-3.96								
	Sliding Door SD, (2000 X 2100)	-1.00	0.60		0.60	-0.36								
	Sliding Door SD, (2000 X 2100)													
	Window W, (1800 X 1200)	2.00	2.26		1.31	5.92								
	Ventilator V, (600 X 600)	1.00	2.25		1.31	2.95								

PROPOSED RESIDENTIAL BUILDING														
			Length	Breadth	Depth			REMARKS		Shuttering Qty				
I	Water Proofing & Roof tile works													
I.1	Water Proofing & White Cooling Tile works					174.00	Sqm							
	Terrace	1.00		174.00		174.00								
I.2	Cooling Tile Skirting works					80.00	Rm							
	Terrace	1.00		80.00		80.00								